

IMPLEMENTATION

OF

A CONSTRUCTION ENGINEERING MANPOWER MANAGEMENT SYSTEM

FHWA CONTRACT NUMBER DOT-FH-11-9122

FINAL REPORT

PREPARED FOR

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION OFFICES OF RESEARCH AND DEVELOPMENT IMPLEMENTATION DIVISION

SUBMITTED BY

MINNESOTA DEPARTMENT OF TRANSPORTATION

OPERATIONS DIVISION

FEBRUARY 1982

PROPERTY OF MN/DOT LIBRARY, Minnesota Department of Transportation

MNDOT HD 9715 .A2 K673 1982 C.2



NOTICE

This document is disseminated under the sponsorship of the Federal Highway Administration in the interest of information exchange. The United States Government assumes no liability for its contents or use thereof.

The contents of this report reflect the views of the Minnesota Department of Transportation, who is responsible for the facts and data presented herein. The contents do not necessarily reflect the official views or policy of the Federal Highway Administration. This report does not constitute a standard, specification or regulation.

H5H a5 371 Technical Report Documentation Page

. Le /

V

• • •		rechinedr hepoir pocomentation rage				
1. eport No.	2. Government Accession No.	3. Recipient's Catalog No.				
F'HWA-TS-812						
4. Title and Subtitle	4. Title and Subtitle					
Implementation of a C Manpower Management S	6. Performing Organization Code					
7. Author(s)		8. Performing Organization Report No.				
Gerald Kopacek, P.E.,	L.S.	•				
9. Performing Organization Name and Addres	is	10. Work Unit No. (TRAIS)				
Minnesota Department Transportation Buildi St. Paul, Minnesota	of Transportation ng 55155	 Contract or Grant No. DOT-FH-11-9583 Type of Report and Period Covered 				
12. Sponsoring Agency Name and Address	· · · · · · · · · · · · · · · · · · ·					
U.S. Department of Tr	ansportation	Final Report				
Federal Highway Admir Washington, D.C. 205	990	14. Sponsoring Agency Code				
15. Supplementary Notes						
Contract Manager, Ray	mond F. Bova					
16. Abstroct						
Operations Division of (Mn/DOT). The report the implementation ar problems that might b in other states.	of the Minnesota Departm describes the problems ad makes suggestions for be encountered during co	ent of Transportation encountered during nuetralizing similar omparable implementation				
The CEMMS is designed and estimating constr computer software the The system was design field engineers that	l to provide a uniform m ruction manpower. The s at runs in each of Mn/DO and the system softw use the system.	method for controlling system employs micro- OT's nine districts. ware written by the				
-						
		Х				
17. Key Words	18. Distribution State	ement				
Construction Staffing Manpower Management Micro Computer Softwa Manpower Flanning Manpower Staffing Manpower Monitoring	This docum the Nation Service, S 22161	This document is available through the National Technical Information Service, Springfield, Virginia 22161				
19. Security Classif. (of this report)	20. Security Classif. (of this page)	21. No. of Pages 22. Price				
Unclassified	Unclassified					

Form DOT F 1700.7 (8-72)

.

3

Reproduction of completed page authorized

ACKNOWLEDGMENTS

Richard P. Braun, P.E., L.S. - Commissioner of the Minnesota Department of Transportation

Steering Committee

- W. C. Merritt (Chairman) Assistant Commissioner, Operations Division
 W. M. Crawford - District Engineer, District 5
- L. F. McNamara Assistant Division Director Operations Division

R. G. Brennan - Construction Engineer

P. M. Bergman Contract Administration Engineer

H. S. Grothaus - FHWA Representative

S. O. Edman - Administrative Manager, Operations Division

Technical Panel

Edward Liebe (Chairman) - Assistant District Engineer, District 1

M. E. Sheldrup - Assistant District Engineer, District 7
J. L. Spencer - Assistant District Engineer, District 6
B. A. Larson - Resident Engineer, District 3

Project Staff

D. N. Christensen - Project Engineer, District 6
J. W. Miner - Project Engineer, District 9
G. D. Adkins - Project Supervisor, District 6
G. R. Kopacek - Project Engineer, District 7
R. D. Berg - Senior Technician, District 7

This report was prepared by the Minnesota Department of Transportation under the supervision of Edward Liebe, P.E., Technical Panel Chairman and Paul M. Bergman, P.E., Principal Investigator. Preliminary drafts were prepared by Gerald Kopacek, P.E., Project Staff Member. Draft reviews and edits were made by Edward Liebe, P.E. and Marlyn Sheldrup, P.E., Technical Panel Members and Darrell Christensen, P.E., Project Staff Member.

Computer software was written and documented by Russell Ohm and Kevin Meyer (Mn/DOT District 7).

Special appreciation is expressed to Mary Novotny, Word Processor Operator (District 7), for typing the preliminary and final drafts.

TABLE OF CONTENTS

	. כ
Informational Abstract i	•
Introductionv	,
Chapter One - Organization 1 Background 1 Steering Committee 2 Technical Panel 2 Project Staff 3 Conclusion 3 FHAW Contract Compliance 5	
Chapter Two - System Specifications	
Chapter Three - System Design	

,

Page

		8			
•		•	•		
					•
			•		_
					Page
Cha	apter Four - Implementat	-ion	• • • • • • • • •		.21
	Background			• • • • • • • •	.21
	Pilot Project Implement	tation			.21
	Statewide Orientation.			• • • • • • • •	.23
	Planning				.24
	Staffing				.24
	Scheduling				.24
	Monitoring				.25
	Top Management				.25
	Conclusion		• • • • • • • • •		.25
	FHWA Contract Complian	ce			.26
•				1	
Cha	apter Five - Monitoring				.27
	Background				.27
	Project Level				.27
·	District Level				.28
	Conclusion				.28
	FHWA Contract Complian	ce		• • • • • • • •	.29
Ch	apter Six - System Upda	ting			.30
	Background	•••••			.30
	Planning				.30
	Monitoring				.30
	Work Methods Improveme	nts			.30
	Conclusion				.31
	FHWA Contract Complian	.ce	· • • • • • • • • •		.32
Ch	apter Seven - Recommend	ations and C	Conclusion		.33
011	System Design Recommen	dations			.33
	Implementation Recomme	ndations			.34
	Savings From CEMMS Imr	lementation.			.34
	Conclusion				.35
	CONCTRR 1011				

• • •

Appendix "A"

Mn/DOT Organizational	Chart	.Al-A2
Construction District:	s	A3

Appendix	"B"	Excerpts	from	Mn/DOT	CEMMS	Operations	Manual
Planni	.ng.					· · · · · · · · · · · 1-1	thru 1-35
Schedu	lin	g					and 3-la
Monito	oring	g					and 4-2

Appendix "C" Examples of Mn/DOT CEMMS Computer Print-outs

Page

Informational Abstract

Organization

Rising inflation, increased labor costs, controlling engineering costs and maintaining high quality construction have all required the Minnesota Department of Transportation (Mn/DOT) to implement a Construction Engineering Manpower Management System (CEMMS). The CEMMS is designed as a management tool to control manpower hours, increase manpower efficiency, provide a uniform method of controlling and predicting manpower, and consequently reduce engineering costs. The system will also justify the construction personnel complement to our state legislature.

Twenty-one states pooled funds to develop a model Construction Engineering Manpower Management System during the early 1970s. The study was coordinated by the FHWA and developed by a management consultant (Roy Jorgenson and Associates). Minnesota's CEMMS organization follows the recommended organizational structure applied in the design manual developed during the pooled fund study. The Mn/DOT CEMMS organizational structure is composed of a Steering Committee, Technical Panel, and Project Staff (See Appendix "A" for Mn/DOT Construction Engineering Organizational Charts). The Steering Committee consists of top Mn/DOT construction management personnel. The Technical Panel is composed of top District Contruction Personnel. The Project Staff members are field construction engineers and high level field technicians. The Project Staff was assisted by two parttime computer programmers and a word processor operator.

i

The plan was to implement a pilot project in two of Mn/DOT's nine districts in order to test the system and fine tune it for statewide implementation. The pilot project employed manual bookkeeping methods for planning and monitoring reporting. The manual bookkeeping method employed by the system was awkward and time consuming. Consequently, the decision was made to computerize the system prior to statewide implementation. The Steering Committee authorized the Technical Panel and the Project Staff to do the system analysis and develop the software, i.e. A system designed by field engineers for field engineers. At this time the system is completely computerized and computer generated reports are available for Mn/DOT's engineering managers.

System Specifications and Design

The basic elements of the Mn/DOT-FHWA Contract system specifications were to develop, implement, and monitor a construction engineering manpower management system based on the System Design Manual prepared by the FHWA consultant. The goal was to develop a system whose basic elements are planning, budgeting, scheduling, and monitoring. The Minnesota system also includes staffing and forecasting subsystems, and a system update procedure. The contract specifications required that the entire network be documented in the users manuals as appropriate.

Implementation

The Steering Committee made a solid committment early in the system development to support the technical panel and the project staff during the design and implementation. It was apparent to those involved with the system development that top management was sincerely interested in "finding a better way". The pilot project was implemented in Districts 6 and

ii

7 and one project in District 8 in 1979. These Districts are located in the southern half of Minnesota. The system was implemented statewide in the spring of 1980. Only new projects were placed into the system.

Monitoring

The Mn/DOT CEMMS monitoring function gathers the field information and generates the desired reports. The function employs a single form for gathering the information. The activity is supervised by the field engineers.

The monitoring function generates a report for the Project Engineer and also a report for the Assistant District Engineers (Construction). The monitoring function is completely automated and the reports are generated on the micro-computers residing in each of the nine district offices.

The monitoring function also generates information for manpower forecasting. Factors are derived that compare manhours to dollars by contract type. The factors are generated through a direct comparison that yields an average and through a regression analysis that yields an analytical curve. The comparison procedure consists of calculating the manmonths per \$100,000 of contract value for each contract type.

Summary

The CEMMS Steering Committee is confident that their decision to develop a CEMMS employing field engineers and high level technicians for that development was correct. This unique concept coupled with the small starting size of the system has allowed the Mn/DOT CEMMS to grow into a powerful management tool. Much of the system's success can be

iii

charged to the straight-forward, simple, field manual developed for the statewide implementation. The CEMMS automation applies computer programs that run on district based micro-computers and truly takes advantage of modern microcomputer technology.

Introduction

The final report purpose is to document implementation of Construction Engineering Manpower Management System (CEMMS) in Minnesota. The various system components, implementation problems and implementation procedures are discussed in detail. The report is divided into seven major parts: organization, specifications, design, implementation, monitoring, updating, and recommendations. Excerpts from the operations manual that are pertinent to the report have been included in Appendix "B".

Chapter 1 - Organization

Background

Many state agencies recognized the need to develop manpower management systems, consequently extensive studies to develop such systems began in various states in the early 1970's. Twenty-one state highway agencies, including Minnesota, pooled HPR funds and financed a study to develop a "model" construction engineering manpower management system. The study was coordinated by the FHWA. Roy Jorgensen and Associates (Management Consultants) were selected to design the system. Primary research data sources were Louisiana, Michigan, North Dakota and Washington. The study was limited to construction engineering and work performed at the district office managment levels². Two of the study objectives were to develop a construction manpower management system and a system design manual for interested highway agencies. The study was completed in April of 1978.

The Minnesota Department of Transportation (Mn/DOT) also recognized a need to develop a construction manpower management system. Each of Mn/DOT's nine districts employed unique systems that grew out of management styles peculiar to those districts and a need existed at the State level to implement a uniform method to control and predict construction manpower.

¹ See Report No. FHWA-TS 78-226

² See TRB Report No. 51 "Construction Contract Staffing"

Consequently, in November of 1978 Mn/DOT held a training workshop dedicated to implementing a construction manpower management system. In January of 1979, the Commissioner of Transportation appointed a Steering Committee, Technical Panel and a Project Staff to design and implement such a system for Mn/DOT.

Steering Committee

The Steering Committee is composed of Mn/DOT's top construction managers. They gave the Technical Panel and Project Staff the authority to design and implement the system. The Committee made a solid commitment early in the design process to support the CEMMS concept and the efforts of the Technical Panel/Project Staff. It was apparent to those involved with the system design that top management was sincerely interested in finding a better way to manage and forecast manpower.

The Steering Committee is composed of¹ the Assistant Commissioner Bureau of Operations, the Field Operations Engineer, a District Engineer, the Construction Engineer, the Contract Administration Engineer, a representative of the FHWA, and the Field Operations Administrative Manager.

Technical Panel

The Technical Panel is composed of top district construction personnel. The panel was authorized to develop:

- A time table for implementation.
- The specifications for a CEMM System.
- A procedure for implementing a pilot study in districts 6 and 7.
- A procedure for implementing the system statewide.

¹ See Mn/DOT Construction Organization Chart on Appendix Al

The members of the Technical Panel are Assistant District Engineers (Construction) and a Resident Engineer. They were given this assignment because of their interest and willingness to invest time and effort to develop a worthwhile, meaningful management tool.

Project Staff

The Project Staff is composed of field construction engineers and high level technicians. They were assigned to:

- Prepare an operations manual
- Conduct a pilot project in Districts 6 and 7
- Prepare formal and informal proposals for CEMMS modifications
- Conduct CEMMS workshops in each of the districts prior to the CEMMS statewide implementation.
- Periodically review operation of the system.

The members of the Project Staff were given this assignment because of their construction experience, their dedication to their work, their ability to work with people, their innovative thinking and their acceptance of a new method to deal with construction manpower management.

The Project Staff is composed of three senior engineers, one principal engineering specialist, and one senior highway technician. The Project Staff is assisted by parttime computer programmers and a parttime word processor operator.

Conclusion

After reviewing the FHWA system design manual, Mn/DOT top management recognized that the design manual addressed the construction manpower planning problems found in the Mn/DOT. Since the FHWA design manual was very well written and easily understood, the Mn/DOT Operations Division decided that they could produce a system, and a manual for that system, without outside assistance. Consequently, top management policy was to let the system users design a system that was user oriented, i.e. a system designed by field engineers for field engineers. The system design was started with that concept in mind and that concept is one of the unique aspects of the Minnesota System.

Another interesting aspect regarding the Minnesota System is that none of those assigned to the Project Staff are assigned full-time. During the construction months the construction takes priority over the CEMM System development and maintenance. The remaining months are sufficient to update the System and study the data generated by the System. The System was designed to run at the District level and as a tool primarily for the Engineers engaged in construction activities. However, how that tool is employed is the option of the system users. The data generated by the system is analyzed once each year in order to test the planning values, activity codes, and establish a data bank for generating manpower forecasting factors from the correlation between manhours and contract values. The only necessary staffing is a technician or a computer programmer available to answer questions regarding the software operation. The system reports can be generated every two weeks or at intervals set by the Engineers using the system.

FHWA Contract Compliance

The system was developed on schedule and implemented in accordance with Task A of the FHWA contract. The Technical Panel/Project Staff produced an operations manual for the pilot implementation and subsequently an updated operations manual for statewide implementation.

Chapter Two - System Specifications

Background

The CEMMS Specifications are as follows:

- Develop, implement, and monitor a construction engineering manpower management system for Mn/DOT
- Base the Mn/DOT system design on the system design manual prepared under FHWA contract DOT-FH-11-9122.
- Demonstrate to the highway community the benefit of implementing a CEMM System.
- Develop a complete system, whose basic elements are planning, budgeting, scheduling, monitoring.
- Document specifications and procedures in users manuals.
- Documentation shall include organization, definitions, activities, standards, procedures, resource requirements, and instructions for computer use.

Two manuals were developed, the operations manual and the field operations manual. These two manuals are described in detail in Chapter Three - "Planning" on page 8 of this report.

Conclusion

No problems were encountered during the specification development. The goal, to develop a workable manpower management system, was well defined early in the system organization and development.

System automation was added to Mn/DOT CEMMS. The addition was made:

- To facilitate implementation
- To save manpower during the monitoring function

The quarterly reports required by the FHWA contract were factual and addressed the contract requirements.

Specification changes will be added to this system as more input is generated by the system users.

FHWA Contract Compliance

Mn/DOT system specifications fit those described in task "C" of the statement of work included in the FHWA contract. No extraordinary problems were encountered during the development of the users manuals and the computer software. The "model" system design manual provided by the FHWA was straight forward and covered the major system design problems. The CEMMS pilot study manual and the updated version developed for the statewide implementation were prepared on schedule with the CEMMS implementation plan. The system documentation manual was prepared in accordance with the FHWA contract.

Chapter Three - System Design

Background

Minnesota elected to design their system for the planning, staffing, scheduling and monitoring functions. Forecasting, and updating, were subsequently developed and sub-systems will be added to the operations manual. The design plan was to apply the national pooled fund study recommendations embodied in the FHWA system design manual.

Planning

The title "Construction Engineering Manpower Management System" (CEMMS) seemed to describe the Minnesota system. Consequently, the system title was not changed from the one recommended by the system design manual.

Two CEMMS manuals have been prepared, an operations manual that contains the entire system and a field operations manual that consists of planning, staffing, scheduling, and monitoring sections and that portion of the appendix relating to these activities. The operations manual is placed in the Resident Engineer's office and with the Assistant District Engineer (Construction). The field operations manual is employed at the Project Engineer, Project Supervisor level. All references in this report are to the operations manual.

The Minnesota system is designed to employ two of the methods recommended by the system design manual for planning manpower;

The method of "defined contract quantities" is the most accurate method and is employed when these quantities are known.

The method of "program dollar amounts" is employed when the contract quantities are unknown. This method can be used for long range forecasting, however, the forecast accuracy is controlled by the accuracy of the estimated "program dollar amount" and the program stability.

Planning - Defined Contract Quantities

The nine contract types recommended by the design manual were used for the pilot implementation in District 6 and 7 for the first construction year of statewide implementation. Another contract type (Bridge Replacement) was added during the 1981 system updating process. The contract types are shown on page 1-2 of the operations manual (See Appendix "B"). Definitions for the contract types were modified slightly to better fit the construction conditions found in Minnesota.

The Technical Panel/Project Staff adopted 47 planning activities. The planning activity definitions shown in the design manual were modified to conform to the activities performed in Minnesota. The Mn/DOT Pay Quantity Documentation Manual was used to determine the activity definition modifications.

Mn/DOT Construction Engineering practices made it necessary to modify the standard planning values described in the design manual. The modifications consisted of changing some of the planning values, deleting some, and creating others to fit current construction practices and the Mn/DOT Pay Quantity Documentation Manual. The standard planning values are listed by contract type on pages 1-21 thru 1-35 in the operations manual (See Appendix "B"). The standard planning value computations are found in Appendix A of the operations manual.

The planning units of measure described in the design manual were modified to reflect the planning activity changes, the field and contract conditions, and pay quantity documentation unique to Mn/DOT. A description of the planning units of measure can be found on pages 1-17 thru 1-19 of the operations manual (See Appendix "B").

Minnesota highways are exposed to heavy frost action and large summer-winter temperature differentials that enhance roadway deterioration, consequently materials and workmanship must be of the highest quality. Projects must be adequately staffed to ensure that these high quality standards are satisfied. The Technical Panel/Project Staff adopted near "maximum staffing guidelines" as described in the FHWA Design Manual. The guidelines are reflected in the Mn/DOT standard planning values.

Planning-Program Dollars

Program dollar amounts are employed to plan manpower when the contract quantities are unknown. The procedure relates program dollars to manhours or manmonths for each contract type. The forecasting subsection in this chapter will discuss the subsystem employed by Mn/DOT in detail.

Staffing

Staffing is the second element of the Mn/DOT CEMMS. The staffing process is designed to distribute manpower over the

calendar year. The Mn/DOT staffing process applies the "planning activities-engineering judgment" technique to their method of manpower distribution.

Engineering judgment is exercised to distribute manmonths planned for each project activity on the "Construction Manpower Planning Report" over the calendar year. The distribution is made by the project engineer on the "Annual Construction Project Staffing Plan" (see operations manual page 2-4 Appendix "B"). The staffing plan is employed by the Project Engineer to:

- Identify skill level needs.

Balance manpower skills among projects.

The staffing plan is submitted to the Assistant District Engineer (Construction) and compiled on the "Annual District Construction Staffing Summary" shown on page 2-7 of the operations manual. The summary interpretation is employed by the District Engineer and Assistant District Engineer (Construction) to:

- Balance the employee complement among the resident offices.
- Identify and plan for off season assignments.
- Maximize employee complement effectiveness by adjusting contract letting dates.
- Identify seasonal manpower needs early.
- Identify personnel shortages or excesses.

The summaries are used by Assistant Commissioner of Operations to balance manpower among the Districts.

The Mn/DOT CEMMS does not address staffing by skill levels as outlined in the FHWA Design Manual. However, skill levels are recognized at the project engineer management level when staffing a particular project. The reasons for

not incorporating staffing by skill levels in the Mn/DOT system are as follows:

- Mn/DOT employs a Junior/Senior plan for technician classifications which is, of course, advocated by the strong employee union. The plan provides rapid advancement to the classification of Technician Intermediate (See Organization Chart Appendix "A" page A-2).
 Consequently, Mn/DOT really employs only two levels of technicians in a non-supervisory capacity. Technician certification is not recognized by either the Union or the State, therefore, skill level determination is based on the judgement of the resident and project engineers.
- Most Mn/DOT field technicians have many years of construction experience and possess diversified inspection and surveying skills.
- Field Construction Engineers did not want to obligate to a strict project staffing procedure.

More discussion is planned in the area of skill level determination and staffing by skill levels as outlined in the FHWA Design Manual. An indexing system (not related to CEMMS) is planned for cataloging employees and their particular skills and other studies that address employee skills are being made in Mn/DOT.

More work also remains in the area of staffing from the reduced personnel complement mandated by the State Legislature and justification of future personnel complements. These problems will be considered during the system update process and future system enhancements will reflect these considerations. Some of the considerations may consist of:

- Contractor staking
- End result specifications
- Independent inspection
- Automatic weigh scales
- Reduced testing rates

Scheduling

Scheduling is the third element of the Mn/DOT CEMMS. The scheduling process is designed to employ the "Primary-Secondary Assignment" method. The primary assignment is based on the contractors schedule and is influenced by the weather, equipment breakdowns, short notice changes in the contractors schedule, and other factors. Secondary assignments are intended to provide a smooth transition to useful work on days when the contractor is not working.

Written schedules are not widely used since the resident office staffs are adjusted to the work load at the beginning of the construction season. The resident offices are usually located more than one hour apart and personnel are assigned on a long term basis. The size of most resident offices permits efficient oral scheduling. A list of scheduling benefits may be found on page 3-1 of the operations manual (See Appendix "B").

Monitoring

Monitoring is the fourth element found in the Mn/DOT CEMMS. The process is designed to gather information for the forecasting subsystem, provide information for updating standard planning values, and evaluate work performance. The process also evaluates construction progress and it provides data for making staffing adjustments. The field reporting for the monitoring process is the responsibility of the project

engineer. The monitoring process is based on planning activities and generates three reports. These reports will be covered in detail in chapter Four.

Forecasting

The forecasting subsystem is designed to predict manpower from program or contract dollars. A forecast is made at the state program level, district program level and the project level. The forecast is made by dividing the construction program into the ten contract types recognized by the Mn/DOT CEMMS. The program dollars for each contract type are used to forecast manpower at one of the three levels. The forecasts are based on the average man months per 100 thousand dollars for each contract type.

Future forecasting at the project level will be based on regression equations which will be based on historical data being generated by the monitoring process. The procedure will be as follows:

- 1 Manhours expended are compared to contract dollar amounts for contracts of the same type.
- 2 The analysis is made for each of the ten contract types.
- 3 A graph of the equation is made for each of the contract types to expedite the calculation.
- 4 The equation resulting from the regression analysis is used to calculate manpower for any dollar amount.
- 5 The intent is to update the factors in the graph and to place the revisions into the operations manual.

A factor must be applied to the manpower estimate that reflects the time allowed for vacation, sick leave, and

holidays. The factors are derived in each district from historical data available from the payroll record. That factor in Mn/DOT is approximately 15%. The forecast must also consider the estimated average Minnesota construction season of seven months.

The forecasting subsystem was designed as a tool for top management to predict construction engineering manpower. It is also intended that the subsystem will help predict training needs and will help justify the construction personnel complement. The subsystem can be used as a vehicle to build manpower scenarios and consequently the forecasting system will be sensitive to the rapidly changing construction program.

Budgeting

The budgeting subsystem described in the FHWA Design Manual is not used by the Minnesota Department of Transportation. The described subsystem is not used primarily because the CEMMS staffing process does not address staffing by employee classification or skill level. That task is usually delegated to the Resident Engineer at the time the manpower is divided among the the construction projects. The manpower budget is determined by the personnel complement which in turn is mandated by the State Legislature. At times the District complement need either lags or is ahead of the workload to such an extent that it is necessary to shift men among districts or change the district construction program. The workload is related directly to the annual district construction program. The more that program fluctuates the more difficult it is to staff and budget manpower for construction projects and maintain an adequate complement.

Computer Software

Mn/DOT made an early decision to develop CEMMS computer software for the newly installed district micro-computers. The decision was made to eliminate as much CEMMS "Paperwork" as possible. Another reason was to save time and money, since the only other automation alternate was to program the system to run at the state computer center. The Mn/DOT data processing professionals were busy with other systems and a two year delay would have been experienced. Consequently, the programming was delegated to the project staff members assigned to Construction District 7. The system operations manual generated by the pilot study in District 6 and 7 was used as guide for the program coding. Mankato State University (located at Mankato, Minnesota) is noted for its computer science degrees and two of the intermediate technicians assigned to the District 7 Headquarters (also located at Mankato) had taken some of the computer science courses offered by the University. These two intermediate technicians were given the responsibility of coding the program for the CEMMS software.

The CEMMS software designed for the statewide implementation was completed in April of 1980. The software was enhanced during statewide implementation to include an engineering cost report. A second enhancement was made during the winter of 1980-1981. The enchancement reflected adjustments to the planning values, added one contract type, made major changes to the software architecture, and added a summary printout for the Assistant District Engineers (Construction) (See Appendix "C"). The estimated to date cost of the software developed for the Mn/DOT CEMMS is \$20,000. The program coding took approximately twelve months. It is estimated

that Mn/DOT saved approximately \$100,000 by doing the computer programming by the system users. The reports generated by the software replaced five of seven report forms used in the pilot study, they are:

- Construction Project Manpower Planning Report
- Annual Construction Project Staffing Plan
- Annual District Construction Staffing Plan
- Construction Activity Ledger
- Monthly Construction Project Manpower Report

The automation also saves approximately 1,000 manhours per year by elimination of the manual reporting and bookkeeping.

The software resides on a Texas Instrument Bronco Micro-Computer with a 48K memory and a dual 8" floppy disk drive. The software was written in the basic programming language and it is thought that the program can be easily adopted to other micro-computer systems. Examples of the computer printouts are shown in Appendix "C" of this report.

The software was designed to simplify the planning function for the project engineer. The data processing sequence is as follows:

- Project Engineer requests a computer printout for planning data input for each of his construction projects.
- Project Engineer enters the number of planning units on the computer printout
- Project Engineer sends the printout back to the computer operator.
- Computer operator inputs the data

 Computer prints the "Construction Project Manpower Planning Report" (see Page 1-38 and 1-39 of the Operations Manual) and builds the master file on the "project files" disk.

The software was also designed to simplify the monitoring function as shown by the following data processing sequence:

- Project Engineer submits the "Biweekly Activity Report" (field form) to the computer operator
- Computer operator inputs the data
- The computer prints the "Biweekly Construction Manpower Report" for the Project Engineer
- The computer prints "Monthly Construction Payments and Engineering Costs " for the Assistant District Engineer (Construction).

Software has been developed to facilitate the staffing function as shown by the following data processing sequence:

- Project Engineer requests a computer printout for data input for each of his projects (printout is similar to the "Annual Construction Project Staffing Plan" shown on page 2-4 and 2-5 of the operations manual shown in Appendix "C").
- Project Engineer distributes manpower over the construction season and sends the printout to the computer operator.
- Computer operator enters the data and two reports are printed; the "Annual Construction Project Staffing Plan" and the "District Construction Staffing Summary" (shown on pages 2-4, 2-5 and 2-7 of the operations manual see Appendix "C").

The Mn/DOT CEMMS software creates "Master Files" that contain all the data necessary to print the information con-

tained on the reports shown in Appendix "C". The data contained in the master files can be manipulated, by writing additional software, to provide:

- exception reports

- monitoring of individual activity codes
- monitoring of only personal expense or construction engineering costs

- monitoring of vehicle costs Other reports may require revision of or addition to the master file data.

Another unique aspect of the Mn/DOT system is that the software was developed without help from the data processing professionals from the Mn/DOT Central Office. All systems analysis and program coding was accomplished by the Project Staff and their staff assistants. The procedure truly took advantage of the modern user oriented micro-computers now available on todays computer market. The system design and programming experience gave those associated with the system an understanding of the system's capabilities and a sense of real accomplishment. Therefore, it is suggested that other states use this approach for their software development.

System Updating

The procedures embodied in the Mn/DOT operations manual follow the recommendations included in the FHWA System Design Manual. The procedure provides for updating:

- Contract types
- Planning activities
- Planning units of measure
- Standard planning values
- Procedures for planning, staffing, scheduling, budgeting and forecasting

System updating will be discussed in detail in chapter 6.

Conclusion

The Technical Panel/Project Staff used the FHWA System Design Manual for designing the Mn/DOT CEMMS. The design manual provided an excellent guide, was easily adoptable to the Mn/DOT operations and was easily understood by those involved in the design. The Mn/DOT CEMMS was designed by field engineers for field engineers. The design was started January of 1979 and three months later the operations manual was ready for the pilot implementation in Districts 6 and 7.

FHWA Contract Compliance

The Mn/DOT system design is in accordance with task B of the statement of work included in the FHWA contract. All of the elements included in that task are either incorporated into the Mn/DOT CEMMS or they will be incorporated into the CEMMS No problems were encountered in the very near future. during the system design procedures and all implementation was on schedule. The Mn/DOT CEMMS accomplishes all the elements required by the contract. Computer software was also developed to facilitate the implementation. The computer software development, however, was not part of the FHWA contract. Mn/DOT did not develop a budgeting process in accordance with the guidelines and recommendations embodied in the FHWA System Design Manual. However, a budgeting process is being studied for possible implementation.

Chapter Four - Implementation

Background

The Mn/DOT CEMMS was implemented in two stages. The pilot study was implemented in Districts 6 and 7 and one project in District 8 in the spring of 1979. The system was updated in the period from December 1979 to the Spring of 1980. Difficulties with the system were studied and the appropriate corrections were made. The system was implemented statewide in the Spring of 1980. The decision was made to place only the new projects into the system. This decision rendered the statewide staffing function ineffective, since all projects were not planned and monitored by the CEMMS in 1980.

Pilot Project Implementation

Problems were minimized during the pilot project implementation, because members of District 6 and 7 were assigned to the Project Staff. Forty-four contracts were planned and monitored during the pilot study. During the winter of 1979/80 planning results were analyzed to varify the planning values developed from those found in the FHWA System Design Manual. The analysis indicated a close correlation between the manhours planned and the manhours used. A composite summary of the pilot study in Districts 6, 7 and 8 can be found on page 22 of this report. The Project Staff worked closely with District 9 in order to get "Metro Input"¹ into the system. District 9 has monitored their projects since the spring of 1979 to determine engineering costs. Actual hours used on several of their projects were compared with manhours planned employing the CEMMS planning values.

Minneapolis and Vicinity (District 5) St. Paul and Vicinity (District 9)

COMPOSITE SUMMARY DISTRICT 6, 7 and 8

11-30-79

NO. OF	CONTRACT	PROJECT A	CTIVITIES		CONTR	ACT TIME		CONTRACTOR	PAYMENTS	
CONTRACTS	5 TYPE	PLANNED	USED	96	PLANN	ED USED	8	PLANNED	USED	96
11	1	48,970	44,535	91	958	723.5	76	19,060,325	13,585,182	71
5	2	16,277	14,087	87	. 335	273.8	82	4,367,465	3,467,951	79
4	3	28,755	20,898	73	254	220.6	87	5,131,672	4,850,628	95
1	4	2,748	1,567	57	30	23	77	736,538	621,992	84
2	6	1,754	958	55	50	52.4	105	133,291	132,209	99
5	. 7	1,689	1,417	84	141	88.8	63	428,377	367,187	86
13	8	8,271	3,193	39	418	221.9	53	1,481,473	901,702	61
3	9	8,417	2,218	26	230	126	55	1,296,650	431,377	33
44 (Contracts	116,881	88,873	76	2,407	1,730	72	32,635,791	24,358,228	75

The analysis varified that the CEMMS planning values were close to "On Target" for Minnesota.

Statewide Orientation

In December of 1979, upon recommendation of the Technical Panel/Project Staff, the Steering Committee authorized statewide implementation. Two members of the Project Staff conducted workshops in each district and explained the system to the construction forces. The workshops took place in late January and early February of 1980 at which time the CEMMS Operations Manuals were distributed. After the Workshops most of the questions arising after the workshops were answered by telephone. Special visits were made to those districts requesting special assistance. Some of the potential CEMMS users were not convinced of the System benefits but were willing to "give the System a try". Cooperation is now excellent and enthusiasm for the System is gaining momentum.

Computer software was sent to each district in May of 1980. The software facilitated the planning and monitoring functions. Initially some of the Resident Engineers elected not to use the micro-computer facilities at their district headquarters and the system was operated manually. However, all resident offices are now using their computers.

The Project Staff/Technical Panel worked closely with the Assistant District Engineers (Construction) in order to facilitate the implementation. These engineers influence the Construction Operations Division, in developing policy, work methods improvements, specification changes, and other things that effect contract management and staffing. The support of this group helped to minimize resistance to change during the statewide implementation.
Planning

Manpower requirements were planned for all new projects by the engineers in charge of those projects. The planning was facilitated by the computer software written for the microcomputers.

Vehicle assignments are made by the resident engineer for each resident office at the beginning of the construction season. Vehicle assignments are made on a need basis and are not part of the Mn/DOT CEMMS.

Staffing

Since the decision was made to place only new construction projects under the CEMM System, the staffing function could not be fully implemented. All the construction projects in Minnesota should be under the CEMM System during the 1983 construction season at which time the staffing subsystem will be fully operational.

The Mn/DOT CEMMS does not employ the staffing procedures outlined in the FHWA Design Manual. Staffing assessments are restricted to the "Annual District Construction Staffing Summary" found on page 2-7 of the operations manual shown in Appendix "C".

Scheduling

The Mn/DOT scheduling function is restricted to the project engineer level and the decision for formal scheduling is at that level. Scheduling has been tried on limited basis and is not generally employed. Implementation of the scheduling system can be classified as unsuccessful in Minnesota. Failure can be attributed to those elements discussed in the Scheduling section of Chapter Three on page 13 of this report.

Monitoring

Monitoring was implemented manually during the pilot study. It was found that the manual method was ackward and slow. Therefore, the project staff was authorized to develop software for the micro-computers to facilitate the statewide implementation. Those using this system were eager to cutdown on paperwork and their cooperation was readily secured. The only report that has to be hand written generated by the monitoring process is the field reporting form "Bi-Weekly Construction Activity Report" (shown on page 4-2 of the Operations Manual excerpt in Appendix "B").

Top Management Involvement

Four joint meetings of the Project Staff, Technical Panel and the Steering Committee were held during the design and implementation procedure. The meetings provided the Steering Committee with an update of the system progress. Top Management recognized the system benefits and encouraged the Technical Panel/Project Staff members to maintain their progress.

Conclusion

The CEMMS was developed by field engineers for field engineers and consequently those charged with implementation could relate to those responsible for maintaining and using the system. The Mn/DOT system was designed simple, however, it is expected to grow as management needs change. The simple design was one of the main objectives. Another objective was to design software to eliminate some of the "paper work". Cooperation among the Project Staff and the various district CEMMS contact personnel is excellent and CEMMS enhancement implementation problems are minor.

FHWA Contract Compliance

The Mn/DOT CEMMS implementation was accomplished according to the schedule required by task "D" in the contract statement of work.

Chapter Five - Monitoring

Background

Monitoring began during the pilot implementation. The monitoring process permitted those charged with the system development to evaluate the system, identify difficulties, and gather information for a forecasting subsystem. The monitoring process was also used to insure compliance with the Mn/DOT CEMMS procedures.

Monitoring is an ongoing process and provides a continuous evaluation and continuous information for system updating. The process tests the planning values, the contract type definitions, identifies problem areas of inadequate staffing, and it provides staffing information for top management. It also provides information for personnel complement.

Project Level

Monitoring at the project level is supervised by the project engineer and project supervisors. The monitoring process yields a "Bi-weekly Construction Project Manpower Report" for each construction project. The report is employed by the project engineer for analyzing his project activity staffing and the progress of the contract. The report lists the to date number of manhours planned and used by project activity; the number of working days planned and used; and the contract funds planned and used during the previous two week period. A copy of the report can be found in Appendix "C".

District Level

The monitoring process also yields a "Monthly Construction Payment and Engineering Cost Report". The report is a summary of the Bi-weekly Construction Project Manpower Reports used by the Project Engineers. The report lists the following data by project:

- Number of manhours planned and used
- Number of working days planned and used
- Contract funds encumbered and used
- Personal expenses
- Engineering costs

The report is employed to determine contract progress and as a management tool for distributing and planning for manpower. The report can also be used at the Resident Engineer level to control manpower and monitor contract progress. The bi-weekly project reports can be requested for any project that is not progressing smoothly.

Conclusion

Analysis of the data generated by CEMMS after the statewide implementation prompted the following recommendations from the Project Staff:

- Add contract type "Bridge Replacement" in order to avoid planning split contracts (Construction and Reconstruction)
- Change some of the planning activities. The changes allow planning activities to better fit contract activities and the construction practices in Mn/DOT.
- Change several of the planning values to reflect more realistic planning for certain contract types.

The above recommendations were implemented in early 1981.

The monitoring process was designed to gather information and is functioning as planned. The information generated (man months/\$100,000 by contract type) is now being used at the state level to forecast manpower needs. Accuracy of the data being generated by the monitoring process can be credited to the deligence and cooperation of the Project Engineers and the Project Supervisors. The Project Staff, during the infancy of this system, has attempted to impress on those using the system the philosophy that with any system, "it's garbage in equals garbage out". The philosophy was effective because the information now being generated is giving the desired result.

FHWA Contract Compliance

The Mn/DOT CEMMS monitoring process is continuous and is intended to support the forecasting subsystem with the information it generates. The monitoring procedure employed by Mn/DOT satisfies the requirement of task "E" in the contract statement of work.

Chapter Six - System Updating

Background

The Mn/DOT CEMMS updating procedure employs the methods suggested in the FHWA System Design Manual. The procedure is performed annually by the Technical Panel/Project Staff. The updates are then incorporated into the operations manual. The system updating work is facilitated thru use of the Word Processor located in District 7.

Planning

The planning process is updated by analyzing the results of the previous construction season. The contract types, planning values or the units of measure, are modified, if necessary, to reflect inconsistencies in planning. The planning values and the units of measure are "fine tuned" at the end of each construction season. Work methods improvements, or changes in construction methods are also considered during the updating process. The planning values or units of measure are modified to reflect the changes. Activity codes are added or deleted as necessary.

Monitoring

The monitoring process update consists of studying the process for better ways to gather field data. The update also studies and develops better methods for analyzing the data generated by the process. The computer printouts are studied for possible improvments and the software is updated accordingly.

Work Methods Improvements

Mn/DOT addresses Work Methods Improvements in three ways none of which are connected to the CEMMS. They are:

- Mn/DOT retains a full time Value Engineer that coordinates preletting value engineering studies for construction projects and coordinates work method improvement studies initiated by the part-time Work Methods Engineer and Technicians assigned to each of the nine districts. The Value Engineer also supervises the Mn/DOT Cost Improvement Program.
- The Mn/DOT Assistant District Engineers (Construction)
 Committee maintains sub-committees that study field construction problems and make recommendations for solutions to those problems.
- The Mn/DOT Construction Practice Advisory Committee studies construction problems, and new construction methods and concepts. The studies result in recommendations for Work Methods Improvements.

Conclusion

The Mn/DOT CEMMS updating process was completed for 1981 in early June. The computer software was also updated to reflect the system changes made in early 1981. The system must constantly change to reflect changes in:

- Complement
- Work Methods
- Union Contracts
- Design
- Policy
- Etc.

If the system is allowed to become obsolete the information generated by the system will be meaningless.

FHWA Contract Compliance

The system update procedure employed by Mn/DOT follows the FHWA Systems Design Manual very closely. The procedure includes all of the elements required by task "B" of the contract statement of work.

Chapter Seven - Recommendations and Conclusions

System Design Recommendations

- Start system small (maybe develop just planning and monitoring the first year) then let system grow as data becomes available.
- Assign well experienced Field Engineers and high level Technicians to the Technical Panel and Project Staff. This will allow the potential system users to design the system and will eliminate the need for training computer consultants or in house computer professionals in engineering jargon and practices. This also minimizes the communication problem usually found between the system designers and the system users.
- Allow micro-computer program coding to be accomplished by those designing the system.
- Require the Technical Panel and Project Staff to Work with all districts in an attempt to satisfy the various management styles and report preferences.
- Keep in mind that user designed systems have a greater chance of success, since "selling" of the system is easier.
- Design an uncomplicated system in a short time show results at the end of the first year after starting work on the system. Some systems take years to complete and some of the top managers retire before the system can give them the information that they need for their decisions.

Implementation Recommendations

- Inform field personnel as to how top management is planning to use the system.
- Do not try to implement computer programs or program modifications until they are working as designed. Such premature implementation can be disasterous.
- Try to secure the cooperation of the Field Engineers through visits to each of the districts and establish good communications between them and the system designers.
- Depend on the influence of top managment to gain some of the cooperation from the field personnel.
- Implement at least the planning and monitoring functions during the first year after the start of the design work.
- Do not try to force system on the Field Engineers and Technicians since without their full support the system will not produce accurate results, confidence in the system will be lost, and the system will fail.
- Try to down play the feeling of "Big brother is watching" i.e. explain to the Field Engineers that the System is designed as a tool for estimating and predicting manpower on a District or at the State level and not as an instrument for scruitinizing individual projects.

Savings From CEMMS Implementation

The only tangible savings that can be recognized at this time is the savings made during the system software develop-

ment and savings made during the subsequent use of the software.

- CEMMS developed by Field Engineers and Technicians \$100,000
- Approximately 1000 manhours per year
 saved by employing CEMMS Software
 1000 hours x \$14.00/hour x 2 years
 \$ 28,000

Some of the intangible savings are preceived as being:

- Better utilization of Construction Manpower by properly distributing the manpower among the Construction Districts.
- Increasing morale and consequently production by maintaining the optimum number of personnel in each District which results in "meaningful work" for everyone and abolishes the need for temporary transfers among the Districts.
- Providing an adequate experienced staff for each construction project which will minimize construction defects and consequently give the public more for their construction dollars.

Conclusion

Success of a CEMMS rests in the hands of Top Management and the Field Engineers. If Top Management does not need or does not use the information generated by a CEMMS then use of the system should be discontinued. The Field Engineers are responsible for gathering the system data and generating

the manpower reports. Consequently, without their cooperation the system cannot function. The input data must be as accurate as possible in order for reports generated by the CEMMS to possess validity and to guarantee that decisions made from the reports will not be based on erroneous data. Success of a CEMMS is a joint effort of all those involved, motivated by a determination to "make it work". , ,

APPENDIX "A"

1.

.

MN/DOT CONSTRUCTION ENGINEERING

ORGANIZATION CHART



* One or more Resident Engineers under each Assistant District Engineer.

** Two or more Project Engineers or Project Supervisors under each Resident Engineer.

Al

Minnesota Department of Transportation

Construction Personnel Classifications

DUTIES District Engineer ENGINEERS/SUPERVISORS Senior Administrative Engineer

Administrative Engineer

TECHNICIANS

Assistant District Engineer Construction

Resident Engineer

Project Engineer

Senior Engineer

Principal Engineer

Project Supervisor Engine Train

Engineer in Principal Training II Or Engineering Specialist

Trainee

Various Construction

Related

Various Construction Related

Various Construction Related

Various Construction Related Engineer in Training I

> Senior Highway Technician

Technician Intermediate

Technician

Seasonal



APPENDIX "B"

Excerpts from the Mn/DOT CEMMS Operation Manual

PART ONE

Planning

The planning function is the first element of the Construction Engineering Manpower Management System. The objective of the planning function is to determine the total manpower for field construction engineering activities. These activities include surveying, inspection, office work, supervision, travel time, and all other work performed by the Engineer and his staff necessary for the satisfactory completion of a project.

The Construction Project Manpower Planning Report (page 1-38) will be initiated in the district by the Resident/Project Engineers. The procedures for developing this report are discussed in detail on pages 1-36 and 1-37 in this section of the manual.

Some advantages to manpower planning include:

- Uniformity Estimates of manpower needs for each project will be based on the standard planning values, consequently, projects will be uniformly staffed.
- 2. Flexibility The Standard Planning Values are the core of the CEMMS and are used to plan the number of manhours for each construction activity. The Technical Panel should consider adjusting those planning values which are obviously wrong for a particular planning activity. Planning values should only be adjusted in very special cases, however, remember that they can be adjusted.
- 3. Control The Engineer has direct control of the manhours used on a project and this planning system is based on manhours derived from contract quantities rather than dollars budgeted for engineering costs.

It is obvious that all Contracts are not alike and that the system must recognize those differences. With this concept in mind the Contracts were separated by their unique characteristics and the similarity of their staffing needs. The various contract types are defined in the following pages.

Contract Types (Detailed Quantities)

MASTER LIST

OF

CONTRACT TYPES

(Detailed Contract Quantities)

Code	Туре
1	Construction*
2	Reconstruction*
3	Bridge Replacement*
4	Widening and Resurfacing*
5	Resurfacing*
6	Bridge Repair*
7	Intersection Improvements*
8	Safety and Traffic Control
9	Miscellaneous
10	Unique

* May be modified to reflect the following exceptional conditions:

- . Under Traffic
- . Urban
- Hilly (Construction, Reconstruction and Bridge Replacement) see page 1-20 for definition of the three modifications.

Occasionally contracts are composed of more than one contract type. The Engineer must recognize this condition and divide the contract into major contract types. A Construction Project Manpower Planning Report is then completed for each of the contract types and the Planning Activity Manhours are then totaled and combined on a composite report.

CONTRACT TYPE DEFINITIONS

Definition

Code

2

1 Construction. New construction of, additions to, or major reconstruction of divided or undivided highways. Includes all major phases of construction--site preparation, earthwork, drainage, structures, paving, etc. -- whether contracted separately or as a complete project. Minor items such as signing, landscaping and guardrail are included unless they are in separate specialty contracts. They are then included in their respective types as defined below.

> New construction -- covers highways built at new locations.

Additions -- includes construction to expand an existing facility such as interchanges, structures, ramps, dual roadways, and rest area sites.

Major reconstruction -- the alteration of an existing facility where earthwork quantities per roadway mile are similar to those for new location construction.

Structures -- includes complete bridges, and may include the removal and replacement of existing structures.

<u>Reconstruction</u>. The removal and replacement, rebuilding or upgrading of an existing roadway. There may be grade changes but normally the changes will not be significant. Includes all phases of construction. May include short relocations. Includes widening equivalent to one lane width or wider. Includes structures when decks are widened and substructures extended.

Definition

- 3 <u>Bridge Replacement</u>. The removal and replacement of an existing bridge and reconstruction of the adjacent roadway. Includes all phases of Construction. May include short relocations and/or widening of the inplace roadway. This contract type is intended for use on projects that are less than one mile in length.
- Widening and Resurfacing. Widening and resurfacing of existing highway facilities when the total added width is equivalent to less than one lane width and grades are not changed. Includes minor grading, extending culverts, curb and gutter, etc. Includes bridge deck widening without substructure changes.
- 5 <u>Resurfacing</u>. Overlaying existing highways and surfacing or overlaying existing shoulders with asphaltic material. Includes joint repair, minor widening with asphaltic materials, some base corrections or asphaltic base, curb and gutter replacement, and adjustments at structures, drives and street returns, and turn lanes when they are the only widening on a project. Also includes rebuilding shoulders with aggregate materials. Does not include extensive reconstruction, pavement replacement or construction of new pavements, excavation, utility, or sewer work.
- 6 <u>Bridge Repair</u>. Repair of bridges includes repairs to decks, curbs, rails, beams and structures. If total deck removal and replacement is required, the contract should be classified as reconstruction.
- 7 <u>Intersection Improvements</u>. Minor construction or reconstruction of streets or highways usually requiring fewer than 50 working days for completion. Normally includes some removal, grading, drainage, and paving. May include curb and gutter.

1 - 4

Code

Code 8

Definition

Safety and Traffic Control. Placement or replacement of guardrail, signs, lighting, traffic signals, and other safety and traffic control devices when let on a specialty contract basis. If safety and traffic control devices are included as a part of a major contract type, they should be included under the miscellaneous activities for that type.

- 9 <u>Miscellaneous</u>. Includes all small projects -- which do not fit any of the above types. Includes landscaping, fencing, etc., when let on a specialty contract basis.
- 10 <u>Unique</u>. Includes all large projects which occur so infrequently that separate contract types are not necessary. Includes construction of buildings for rest areas, offices, scale houses, tunnels, etc.

PLANNING ACTIVITIES

Planning activities are used to describe work that must be performed by field construction personnel on the various types of contracts. A master list of those activities has been compiled and is intended to cover only those activities that require a significant number of manhours. Only those planning activities that apply to a project should be used when doing the manpower planning report.

Activities that are not performed by field construction personnel have been omitted. Examples include:

- Inspection at culvert producing plants performed by District or Central Office personnel.
- Densities and gradations performed by District Laboratory personnel on base and bituminous work.

The Master List of Individual Planning Activities and their definitions follows:

MASTER LIST

INDIVIDUAL PLANNING ACTIVITIES

Code Description EARTHWORK

- 01 Roadway Layout Staking
- 02 Cross-Sectioning and Slope Staking
- 03 Grade Control -- Subgrade
- 04 Removal and Relocation Inspection
- 05 Earthwork Inspection
- 06 Density -- Earthwork and Drainage
- 07 Preparation for Construction -- Office
- 08 Earthwork -- Office

DRAINAGE

- 11 Drainage Structure Staking
- 12 Drainage Structure Inspection
- 13 Drainage Structure -- Office
- 14 Cast-in-Place Box Culvert Staking
- 15 Cast-in-Place Box Culvert Inspection
- 16 Cast-in-Place Box Culvert Inspection-Office

AGGREGATE

- 21 Line/Grade Control -- Aggregate Construction/Paving
- 22 Aggregate Construction Inspection
- 23 Density -- Aggregate Construction
- 24 Gradation -- Aggregate Construction
- 25 Weigh Aggregate Materials
- 26 Check Aggregate Construction Materials
- 27 Aggregate Construction -- Office

ASPHALT PAVING

- 31 Asphalt Paving Inspection
- 32 Asphalt Plant Inspection
- 33 Weigh/Check Asphalt Mixture
- 34 Asphalt Paving -- Office

Code Description

PCC PAVING

- 41 Portland Cement Concrete Paving Inspection
- 42 PCC Plant Paving
- 43 Joint Repair Inspection
- 44 PCC Paving Office

STRUCTURE

- 51 Structure Staking
- 52 Structure Inspection
- 53 PCC Plant Structure
- 54 Structure Office

MISCELLANEOUS

61	Staking Miscellaneous Items
62	Inspection of Miscellaneous Items
63	Office Work for Miscellaneous Items
64	R/W Staking and Monumentation
65	Staking Turn Lanes
66	Inspection for Turn Lanes

67 Office Work for Turn Lanes

SPECIAL FEATURE

- 71 Special Feature Staking
- 72 Special Feature Inspection
- 73 Special Feature -- Office

GENERAL

- 81 General Office Work
- 82 Project Supervision and Management
- 83 Standby
- 84 Travel

INDIVIDUAL PLANNING ACTIVITY DEFINITIONS

Description

EARTHWORK

Code

- 01 <u>Roadway Layout Staking</u>. Staking for road layout includes locating or re-establishing control points, staking or restaking centerline, establishing reference lines, and elevation control; staking for clearing, grubbing, tree removal and miscellaneous items; right-of-way staking; and staking for all utility relocation and construction. FIELD WORK ONLY. (SEE CODE 21)
- 02 <u>Cross Sectioning and Slope Staking</u>. Re-establishing centerline, slope staking, cross sectioning and final measurements for roadway earthwork. Includes cross sectioning of borrow pits, subcut areas and channel changes. FIELD WORK ONLY.
- 03 <u>Grade Control -- Subgrade</u>. Re-establishing centerline, setting offset stakes, and establishing grade for roadway excavation, and embankment. FIELD WORK ONLY. (SEE CODE 21)
- 04 Removal and Relocation Inspection. Inspection of clearing and grubbing, building or structure relocation or demolition; relocation of all utilities and new utility construction of water lines, electrical cables, sanitary sewers, and other removal items. FIELD WORK AND FIELD DOCUMENTATION ONLY.
- 05 <u>Earthwork Inspection</u>. All earthwork inspection, including topsoil removal, stockpiling, and placing inspection; slope shaping and grade inspection. Excludes moisture and density testing. FIELD WORK AND FIELD DOCUMENTATION ONLY.

Description

- 06 <u>Density -- Earthwork and Drainage</u>. Density and moisture determination tests on earthwork and drainage construction.
- 07 Preparation for Construction -- Office. All office engineering necessary to prepare for road layout staking, utility relocation, clearing and grubbing, other removal items, and traffic control during construction. Also includes preparation of field books, sketches, and computations required to determine final quantities for these items of work. FIELD PERSONNEL ONLY
- 08 <u>Earthwork -- Office</u>. Office work in the preparation of slope stake books, grade books, and the computation and preparation of final quantities for earthwork. FIELD PERSONNEL ONLY

DRAINAGE

Code

- 11 Drainage Structure Staking. Layout, staking, and final measurements for all subsurface drainage, pipes, underdrains, storm sewers, headwalls and other related drainage facilities. Excludes cast-in-place box culverts. FIELD WORK ONLY.
- 12 Drainage Structure Inspection. Inspection for installation of pipes, under drains, storm sewers, headwalls, manholes, catch basins and other related minor structures. Includes inspection of installation -- location, trench width, bedding, placement and joints; and inspection of backfill. Includes gradation testing for backfill material. Excludes cast-in-place box culverts. FIELD WORK AND FIELD DOCUMENTATION ONLY.

Description

- 13 Drainage Structure. Office work in the preparation of field book, grade computations, checking documentation and preparation of final quantities for all drainage structures. Excludes cast-in-place box culverts. FIELD PERSONNEL ONLY
- 14 <u>Cast-in-Place Box Culvert Staking</u>. Layout staking and final measurements.
- 15 <u>Cast-in-Place Box Culvert Inspection</u>. Inspection for bedding, forms, reinforcing steel, and backfill. Includes gradation and density tests for bedding and backfill materials and all field plant concrete inspection.
- 16 <u>Cast-in-Place Box Culvert Inspection Office</u>. Office work in the preparation of field books, grade computations, checking documentation and preparation of final quantities. FIELD PERSONNEL ONLY

AGGREGATE

Code

- 21 <u>Line/Grade Control--Aggregate Construction/Paving</u>. Resetting reference lines, setting offset stakes, setting grades, and final measurements for all aggregate construction and paving courses. FIELD WORK ONLY. (This code may not be needed if codes 01 and 03 are used)
- 22 Aggregate Construction Inspection. Inspection of aggregate bases and surface courses. Includes subgrade preparation for aggregate placing; computing and checking yield, inspecting aggregate placing, shaping and width, depth and crown checks. Excludes testing. FIELD WORK AND FIELD DOCUMENTATION ONLY.

Description

- 23 <u>Density -- Aggregate Construction</u>. Field density testing for aggregate bases or surface courses on the roadway. Includes moisture and density tests. By project personnel only.
- 24 <u>Gradation -- Aggregate Construction</u>. Field gradation testing for aggregate bases or surface courses at the aggregate source and on the roadway.
- 25 <u>Weigh Aggregate Materials</u>. Weighing of aggregates for aggregate base and surface construction.
- 26 <u>Check Aggregate Materials</u>. Street checking of aggregates for aggregate base and surface construction.
- 27 <u>Aggregate Construction -- Office</u>. Office work, checking documentation and preparation of final quantities for all aggregate base and surface construction. FIELD PERSONNEL ONLY

ASPHALT PAVING

Code

- 31 <u>Asphalt Paving Inspection</u>. Roadway inspection of asphalt paving operations. Includes checking grade preparations; inspection of contractor's equipment, tacking, joints, mix placement, mix temperature, and rolling. Includes field testing on the roadway. FIELD WORK AND FIELD DOCUMENTATION ONLY.
- 32 <u>Asphalt Plant Inspection</u>. All plant testing and inspection for asphalt paving operations. Includes aggregate gradation tests, spot checks, plant calibration checks, and inspecting methods of storing and stockpiling materials.

Description

- 33 <u>Weigh/Check Asphalt Mixture</u>. Weighing asphalt material mixture (scaleman) collecting weigh tickets (street checker).
- 34 <u>Asphalt Paving -- Office</u>. Office work in the preparation of field books, checking weigh ticket tally accumulation sheets, checking documentation, and preparation of final quantities for asphalt paving. FIELD PERSONNEL ONLY

PCC PAVING

Code

- 41 <u>Portland Cement Concrete Paving Inspection</u>. Roadway inspection of Portland cement concrete paving operations. Includes checking grade preparation, inspection of forms condition and placement, inspection of methods of storing and handling material, inspection of contractor's equipment, inspection of installation of transfer devices, inspection of steel placement and concrete placement--including finishing, edging, curing, straight-edging, grinding, sawing and joint installation. Includes field concrete testing on the roadway. FIELD WORK AND FIELD DOCUMENTATION ONLY.
- 42 <u>PCC Plant -- Paving</u>. All plant testing and inspection for concrete paving operations. Includes aggregate gradation and moisture determination tests.
- 43 Joint Repair Inspection. Inspection of joint repair operations. Includes layout of pavement to be removed; and the inspection of sawing of joints, subgrade preparation and placement of concrete or asphalt pavement. FIELD WORK AND FIELD DOCUMENTATION ONLY.
- 44 <u>PCC Paving -- Office</u>. Office work in the preparation of field books, checking documentation and preparation of final quantities for all concrete paving. FIELD PERSONNEL ONLY

Description

.....

Code

STRUCTURE

- 51 <u>Structure Staking</u>. All layout of structures with a clear span of 20 feet or more. Includes staking working points and establishing vertical control. FIELD WORK ONLY.
- 52 <u>Structure Inspection</u>. Inspection of structures with a clear span of 20 feet or more. Includes inspection of structures excavation and backfill, inspecting piling operations, inspecting reinforcing and structural steel placement, stool shots and determining stool heights, inspecting substructure and superstructure concrete placement, and inspecting project cleanup. Includes all field testing and materials control at structure site. FIELD WORK AND FIELD DOCUMENTATION ONLY.
- 53 PCC Plant -- Structure. All plant testing and inspection of concrete for the construction of structures with a clear span of 20 feet or more. Includes aggregate gradation and moisture determination tests.
- 54 <u>Structure -- Office</u>. Office work in quantity computations, field book preparation, checking documentation, deck grade computations, and preparation of final quantities for structures with a clear span of 20 feet or more. FIELD PERSONNEL ONLY

MISCELLANEOUS

61 <u>Staking Miscellaneous Items</u>. Staking for fence, traffic control, permanent signs, curb, gutter, guardrail and all other items not identified in other activities. Includes all staking on smaller projects such as landscaping, intersection improvements, and safety and traffic control. FIELD WORK ONLY.

```
Description
```

Code

- 62 Inspection of Miscellaneous Items. All inspection, testing and final measurement for curb, gutter, sodding, seeding, erosion control, guardrail, fence, permanent signs, delineators, riprap, striping, final trim and cleanup, and other items not identified in other inspection activities. Includes all inspection on smaller projects such as landscaping, intersection improvements and safety and traffic control.
- 63 Office Work for Miscellaneous Items. Office work in the preparation of field books, checking documentation and preparation of final quantities for signs, seeding, sodding, guardrail, fence, and other items not identified in other office activities. FIELD PERSONNEL ONLY
- 64 <u>R/W Staking and Monumentation</u>. Includes all survey work necessary to establish the R/W and monument locations.
- 55 <u>Staking Turn Lanes</u>. All survey work necessary to stake turn lanes including cross-sectioning, slope staking and drainage staking.
- 66 Inspection for Turn Lanes. All inspection for drainage, earthwork, and turf establishment.
- 67 <u>Office Work for Turn Lanes</u>. Office work for drainage, earthwork and turf establishment including preparation of field books, and preparation and checking of final quantities.

Description

SPECIAL FEATURE

Code

- 71 <u>Special Feature Staking</u>. Staking of major features unique to the projects. Includes all staking for rest area facilities such as buildings, wells, flow chambers, and pump houses; also staking for barriers, tunnels, retaining walls, and other specialty contract items. Includes staking on unique projects. FIELD WORK ONLY.
- 72 <u>Special Feature Inspection</u>. Inspection of major features unique to the projects. Includes all inspection for rest area facilities such as buildings, wells, flow chambers, and other specialty items. Includes inspection of unique projects.
- 73 <u>Special Feature--Office</u>. Office work for major features uni que to the projects. Includes all office work for rest area facilities such as buildings, wells, flow chambers, and pump houses; also barriers, tunnels, retaining walls and other contract items. Includes office work for unique projects. FIELD PERSONNEL ONLY

GENERAL

81 <u>General Office Work</u>. General office work in establishing and maintaining files and record keeping systems; preparation of reports, final "As Constructed" plans, time sheets; and maintaining the office. Includes all office work on projects such as deck repair, landscaping, intersection improvement and safety and traffic control.

Description

Code

- 82 Project Supervision and Management. Project management relative to supervision of surveying, inspection and office activities; meeting with representatives of other divisions or agencies, contractors, land owners, or the public; personnel management, manpower evaluations, training, and other project management including travel time. Note: In most cases the usage of this activity will be confined to the Project Engineer or persons acting as his designated representative for substantial periods of time.'
- 83 <u>Standby</u>. All non-productive time equal to or greater than one hour, spent while waiting for the contractor to commence or resume work, waiting for the weather to improve so work may commence or continue, or other nonproductive time for any reason.
- 84 <u>Travel</u>. Travel time equal to or greater than one hour per person per day.
- NOTE: Inspection of signs, barricades, lighting, detours, and temporary roads needed to maintain traffic flow during construction is included in each inspection activity.

PLANNING UNITS OF MEASURE

A Planning Unit of Measure is the "yardstick" used for measuring the engineering work required for each Individual Planning Activity. Individual Planning Activities are related to the contract types through the planning units of measure.

DEFINITIONS OF PLANNING UNITS OF MEASURE FOR INDIVIDUAL ACTIVITIES

<u>Roadway Mile</u> is the linear length of a roadway of independent, or relatively independent, alignment. Multiple-lane, divided or undivided highways are considered as two roadways. The number of lanes is not important -- as shown by the examples below.



A two-lane highway is one roadway.



A ramp or connecting road is a roadway. The above example shows two roadways -- main line and ramp.



An undivided multilane highway is two roadways.

The number of roadway miles is not necessarily equal to project length. On projects where the number of roadway miles is less than one use one roadway mile for the number of planning units on the Construction Project Manpower Planning Report.

Definitions

10,000 Cubic Yards is a unit based on Earthwork quantities. The quantities include only those excavation and borrow items shown in the contract proposal.

· ,

Each Individual Box Culvert Locations, without regard to number of barrels.

1,000 Tons is based on bid item quantities which are used for aggregate construction and asphalt paving inspection.

1,000 Square Yards is based on bid item quantities which are used for Portland cement concrete pavement.

100 Square Yards is based on bid item quantities which are used for joint repair on Portland cement concrete pavement.

<u>Span-Lane</u> is the number of spans multiplied by the number of lanes of each structure with a clear span of 20 feet or more. When the bridge shoulder width is 8 feet or more, the shoulder shall be considered as another lane.

Bent is the number of substructure abutment or pier locations. It is used for structure staking on major contracts.

<u>Span</u> is the number of spans on a structure with a clear span of 20 feet or more. It is used on bridge repair contracts.

Lump Sum is used for special features on major or unique contracts.
<u>Working Day</u> is the number of working days allowed or estimated for the contract to be completed. It is used on the minor contracts-intersection improvements, landscaping, and safety and traffic control.

<u>Percent of Sum of Man-Hours for Inspection Activities</u> is used for General Office Work. It is a standard allowance based on the total number of direct man-hours planned for all inspection activities.

Standard Planning Values

Standard planning values uniformly quantify the work which must be performed by field construction engineering personnel. Standard planning values have been established to determine the construction engineering manpower requirement for each contract type and planning activity. Each standard planning value is composed of a base planning value plus necessary modifiers. The base planning value represents the construction engineering effort (in manhours) per unit of measure for a standard construction project (rural with no traffic). The modifiers reflect additives to the base planning value. Modifers are added to the base planning values when projects are constructed under traffic, in urban areas, or in hilly terrain. The application of those modifers is described as follows:

<u>Under Traffic</u> - should be applied selectively to planning values for activities on only that portion of the project that carries traffic while construction operations are in progress.

<u>Urban Modifer</u> - applied to planning values for activities on projects or segments of projects that contain utilities and other structures usually found in well developed urban areas. The corporate limits of a city or municipality should not be considered when determining whether to apply the urban modifier.

<u>Hilly</u> - used to describe the project topography and the modifier is applied to planning values for activities on projects or segments of projects that have an average cut and/or fill exceeding 10 feet on centerline.

Indiscriminate use of the planning value modifiers will result in large planning errors and consequently sound judgement must be applied to achieve accurate results. Appendix A contains the Standard Planning Value Computations. The computations show the reasoning used to determine the manhours needed per planning unit for each of the Base Planning Values in the tables. An attempt was made by the Authors to incorporate the testing rates set forth in the "Schedule of Testing" and the testing procedures described in the various manuals into the Standard Planning Values. An attempt was also made to adapt the planning values to the field conditions found in Minnesota. The intent of the Technical Panel is to review the Standard Planning Values on a yearly basis and to revise those that seem to be yielding unrealistic results.

The next fifteen pages contain the table of Activity **Planning** Standards for each of the Contract Types.

TABLE OF ACTIVITY PLANNING STANDARDS Contract Type - Construction

.

			* Base	Modif	ier	
			Planning	Under		
Code	Description	Planning Unit	Value	Traffic	Urban	Hi
EARTHWORK						
01	Roadway Layout Staking	Roadway Mile	127	32	32	
02	Cross Sectioning & Slope Staking	Roadway Mile	68	17	17	-
03	Grade Control Subgrade	Roadway Mile	64	13	12	-
04	Removal and Relocation Inspection	Roadway Mile	17	12	13	
05	Removal and Relocation inspection	Roadway Mile	17	0	1/	
05	Dareite East I D	10,000 c.y.	8.	2	8	
00	Density Earthwork & Drainage	Roadway Mile	25	0	25	
07	Preparation for Const Office	Roadway Mile	21	0	15	
08	Earthwork Office	Roadway Mile	44	· 0	0	
DRAINAGE						
11	Drainage Structure Staking	Roadway Mile	43	6	15	
12	Drainage Structure Inspection	Roadway Mile	28	7	28	-
13	Drainage Structure Office	Roadway Mile Roadway Mile	11	,	11	1
14	Cast-in-Place Box Culvert Staking	Roadway Mile	11	0	11	
14	Cast in Place Box Guivert Staking		48	1	1/	
L J	Last-in-Place Box Culvert	Each	105	26	26	1
16	Cost is Place Box Oulers t	F 1		· •		
10	Cast-in-Flace Box Culvert	Each	11	0	0	
	Office					
AGGREGATE						
21	Line/Grade Control Aggreg.	Roadway Mile	53	8	13	
	Const/Paving	Roadway mile))	0	15	
22	Aggregate Construction Inspection	Roadway Mila	1.1.	12	20	
22	Density Acaroa Construction	Roadway Mile	44	10	22	
23	Density Aggreg. Construction	koadway Mile	12	0	12	
24	Gradation Aggreg. Construction	1,000 Ton	1	0	1	
25	Weigh Aggregate Materials	1,000 Ton	5	2	2	
26	Check for Agg. Materials	1,000 Ton	5	2	2	
27	Aggregate Construction Office	Roadway Mile	2	0	0	
ASPHALT PAV	ING			• • • • • • • • • • • • • • • • • • • •		
31	Asphalt Paving Inspection	1 000 Tons	6	2	3	
32(1)	Asphalt Plant Inspection	1,000 Tons	7	2	5	
32(1)	Weigh/Check Asphalt Mix	1,000 Tons	10	2	4	
27	Asshalt Devise Office	1,000 Ions	10	. 3	5	
54	Asphalt Paving - Office	1,000 Tons	2	0	U	
PCC PAVING	₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩					
41	Portland Cement Concrete Paving	1,000 Sq. Yds.	. 4	1	2	
	Inspection	, <u>,</u>				
42(1)	PCC Plant - Paving	1.000 Sc. Yds.	3	1	2	
44	PCC Paving - Office	1 000 Sq. Yds.	1	0	ñ	
		1,000 by. 105.	· ·	U	Ŭ	
STRUCTURE						
51	Structure Staking	Bent	24	6	6	
52	Structure Inspection	Span-Lane	63	0	0	
53(1)	PCC Plant Structure	Span-Lane	12	0	0	
54	Structure Office	Span-Lane	18	õ	ñ	
			~~	v	v	
MISCELLANEO	US					
61	Staking Misc. Items	Roadway Mile	23	6	8	
62	Inspection for Misc. Items	Roadway Mile	30	8	15	
63	Office Work for Misc. Items	Roadway Mile	34	0	0	

* Manhours/Planning Unit

TABLE OF AC	LIAILA	PI	LANNING	STANDARDS
Contrac	t Type	-	Constru	uction

			* Base	Modifier	-
0 - 1 -			Planning	Under	
Lode	Description	Planning Unit	Value	Traffic	Urban
GENERAL					
81(2)	General Office Work	Insp. MH	15%		
82	Project Super. and Management	MH Act. 01-81	10%		
83	Standby	MH Act. 01-81	02%		
84(3)	Travel One Way				
	0 - 15 Min.	Staking & Insp.	MH 0%		
	20 - 45 Min.	Staking & Insp.	MH 15%		
	More Than 45	Staking & Insp.	MH 25%		

* Manhours/Planning Unit

- (1) Central inspection activities (District 5 and 9 only) omit activities 32, 42, 53, and 50% of 33.
- (2) The Planning Unit for Activity Code 81 is the sum of the manhours required for Activity Codes 04, 05, 06, 12, 15, 22, 23, 24, 25, 26, 31, 32, 33, 41, 42, 52, 53, and 62.
- (3) The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Codes 01, 02, 03, 11, 14, 21, 51, 61, plus the Planning Unit for Activity Code 81.

TABLE OF ACTIVITY PLANNING STANDARDSContract Type - Reconstruction

*			* Bas	e Modi	fier	
			Planning	Under		
Code	Description	Planning Unit	Value	Traffic	Urban	Hil
EARTHWORK			~~~~~~ <u>~</u> ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	<u> </u>		
01	Roadway Layout Staking	Roadway Mile	94	24	24]
02	Cross Sectioning & Slope Staking	Roadway Mile	61	15	15	1
03	Grade Control Subgrade	Roadway Mile	64	13	13	-
04	Removal and Relocation Inspection	Roadway Mile	21	0	32	
05	Farthwork Inspection	Roadway Mile	80	20	80	1
05	Donaity Farthuark & Drainago	Roadway Mile	30	20	30	-
00	Density Earthwork & Dialhage	Roadway Mile	21	0	20	
07	Preparation for Const Office	Roadway Mile	21	0	21	
08	Earthwork Office	Roadway Mile	44	U	0	
DRAINAGE						
11	Drainage Structure Staking	Roadway Mile	54	8	19	
12	Drainage Structure Inspection	Roadway Mile	25	6	50	
13	Drainage Structure Office	Roadway Mile	17	0	17	
14	Cast-in-Place Box Culvert Staking	Roadway mile	2/	4	- 2	
14	Cast in Flace box oulvert Staking	Each	54	14	14	
15	Cast-in-Place Box Culvert	Lach	54	14	14	
14	Inspection	n 1	1 1	0	0	
16	Cast-in-Place Box Culvert	Each	11	0	U	
	Office					
AGGREGATE						<u></u>
21	Line/Grade Control Aggreg.	Roadway Mile	53	8	13	
~~ ·	Const/Paving			-		
22	Aggregate Construction Inspection	Roadway Mile	44	13	22	
23	Density Aggreg. Construction	Roadway Mile	12	0	12	
25	Gradation Aggreg Construction	n = 1 = 0.00 Top	1	n N	1	
24	Woigh Aggregate Materials	1 000 Ton	5	2	2	
25	Weigh Aggregate Materials	1,000 100	5	2	2	
20	Check for Agg. Materials	1,000 10h	ر م	2	2	
27	Aggregate Construction Office	Roadway Mile	2	U	U	
ASPHALT PA	VNG					
31	Asphalt Paving Inspection	1.000 Tons	6	2	3	
32(1)	Asphalt Plant Inspection	1.000 Tons	7	2	4	
33(1)	Waigh/Chack Asphalt Mix.	1 000 Tons	10	3	5	
2/	Acabalt Powing - Office	1,000 Tone	20	0	Ő	
54	Asphalt Faving - Office	1,000 1005	L	U	0.	
PCC PAVING			· · · · · · · · · · · · · · · · · · ·			
41	Portland Cement Concrete Paving	1,000 Sq. Yds.	4	1	2	
•	Inspection					
42(1)	PCC Plant - Paving	1,000 Sq. Yds.	3	1	2	
43	Joint Repair Inspection	100 Sa. Yds.	22	0	11	
44	PCC Paving - Office	1.000 Sa. Yds.	1	0	0	
		-,	-	-		
STRUCTURE						
51	Structure Staking	Bent	8	1	0	
52	Structure Inspection	Span-Lane	58	0	0	
53(1)	PCC Plant Structure	Span-Lane	11	0	• 0	
54	Structure Office	Span-Lane	16	0	0	
		۰ - · · · · · · · · · · · · · · · · · ·				
MISCELLANE	OS				~	
61	Staking Misc. Items	Roadway Mile	23	6	8	
62	Inspection for Misc. Items	Roadway Mile	26	7	26	
63	Office Work for Misc. Items	Roadway Mile	34	0	0	

TABLE OF ACTIVITY PLANNING STANDARDS Contract Type - Reconstruction

			* Base	Modifier	
			Planning	Under	
Code	Description	Planning Unit	Value	Traffic	Urban
GENERAL					
81(2)	General Office Work	Insp. MH	15%		
82	Project Super. and Management	MH Act. 01-81	10%		
83	Standby	MH Act. 01-81	02%		
84(3)	Travel One Way				
	$\overline{0 - 15}$ Min.	Staking & Insp.	мн 0%		
	20 - 45 Min.	Staking & Insp.	MH 15%		
	More Than 45	Staking & Insp.	MH 25%		

* Manhours/Planning Unit

- (1) Central inspection activities (District 5 and 9 only) omit activities 32, 42, 53, and 50% of 33.
- (2) The Planning Unit for Activity Code 81 is the sum of the manhours required for Activity Codes 04, 05, 06, 12, 15, 22, 23, 24, 25, 26, 31, 32, 33, 41, 42, 43, 52, 53, and 62.
- (3) The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Codes 01, 02, 03, 11, 14, 21, 51, 61, plus the Planning Unit for Activity Code 81.

TABLE OF ACTIVITY PLANNING STANDARDSContract Type - Bridge Replacement

5 1 1

-		· •	* Bas	se Modi	fier	
			Planning	g Under		
Code	Description	Planning Unit	Value	Traffic	Urban	Hil
EARTHWORK						
01	Roadway Layout Staking	Roadway Mile	94	24	24	14
02	Cross Sectioning & Slope Staking	Roadway Mile	61	15	15	1:
03	Grade Control Subgrade	Roadway Mile	64	13	13	(
04	Removal and Relocation Inspection	Roadway Mile	32	0	32	
05	Earthwork Inspection	Roadway Mile	90	22	90	15
06	Density Farthwork & Drainage	Roadway Mile	33	0	22	
07	Preparation for Const Office	Roadway Mile	21	0	21	
08	Earthwork Office	Roadway Mile	33	· 0	0	Ì
DRAINACE						
11	Drainago Structure Staking	Ponduray Mila	27	5	14	1
10	Drainage Scructure Staking	Roadway Mile	27	ر ہ	14	1.
12	Drainage Structure Inspection	Roadway Mile	30	0	10	1
13	Drainage Structure Office	Roadway Mile	13	Ů	13	
14	Cast-in-Place Box Culvert Staking	Each	24	4	8	
15	Cast-in-Place Box Culvert	Each	54	14	14	
16	Cast-in-Place Box Culvert Office	Each	11	0	0	(
AGGREGATE		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	· · · · · · · · · · · · · · · · · · ·			
21	Line/Grade Control Aggreg. Const/Paving	Roadway Mile	53	8	13	
22	Aggregate Construction Inspection	Roadway Mile	44	13	22	1
22	Density Aggreg Construction	Roadway Mile	12	10	12	
25	Cradation Acaroa Construction	n 1 000 Ton	12	0	12	
24	Gradation Aggreg. Construction	1 000 Ton	1	0	1 2	
25	Weigh Aggregate Materials	1,000 100	5	2	2	
20	Check for Agg. Materials	1,000 10n	2	2	2	
27	Aggregate Construction Office	Koadway Mile	Z	. 0	0	(
ASPHALT PA	VNG					
31	Asphalt Paving Inspection	1,000 Tons	6	2	3	
32(1)	Asphalt Plant Inspection	1.000 Tons	7	2	4	
33(1)	Weigh/Check Asphalt Mix.	1,000 Tons	10	3	5	
34	Asphalt Paving - Office	1,000 Tons	2	0	Ő	
		1,000 1003	۷		0	
PCC PAVING	Portland Coment Concrete Paving	1 000 50 840		1	2	
-1-1	Inspection	1,000 by. Ids.	4	I	2	
42(1)	PCC Plant - Paving	1 000 Sa. Yds.	3	1	2	
42(1)	Toint Panair Inspection	1,000 Sq. 103.		0	11	
45	BCC Bowing - Office	1 000 Sq. 103.	1	0	11	
44	rcc raving - office	1,000 Sq. 185.	1	U	U	
STRUCTURE						
51	Structure Staking	Bent	24	6	6	
52	Structure Inspection	Span-Lane	63	0	0	
53(1)	PCC Plant Structure	Span-Lane	12	0	0	
54	Structure Office	Span-Lane	18	0	0	
MISCELLANE	ous				- <u></u>	
61	Staking Misc. Items	Roadway Mile	23	6	8	
62	Inspection for Misc. Items	Roadway Mile	26	7	26	
63	Office Work for Misc. Items	Roadway Mile	34	0	0	

TABLE OF ACTIVITY PLANNING STANDARDSContract Type - Bridge Replacement

			* Base	Modifier	
			Planning	Under	
Code	Description	Planning Unit	Value	Traffic	Urban
GENERAL	· ·				
81(2)	General Office Work	Insp. MH	15%		
82	Project Super. and Management	MH Act. 01-81	10%		
83	Standby	MH Act. 01-81	02%		
84(3)	Travel One Way				
	$\overline{0 - 15}$ Min.	Staking & Insp.	MH 0%		
	20 - 45 Min.	Staking & Insp.	MH 15%		
	More Than 45	Staking & Insp.	MH 25%		

* Manhours/Planning Unit

- (1) Central inspection activities (District 5 and 9 only) omit activities 32, 42, 53, and 50% of 33.
- (2) The Planning Unit for Activity Code 81 is the sum of the manhours required for Activity Codes 04, 05, 06, 12, 15, 22, 23, 24, 25, 26, 31, 32, 33, 41, 42, 43, 52, 53, and 62.
- (3) The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Codes 01, 02, 03, 11, 14, 21, 51, 61, plus the Planning Unit for Activity Code 81.

TABLE OF ACTIVITY PLANNING STANDARDS Contract Type - Widening & Resurfacing

	<i></i>	8 8	.t. 70	11.01	
			* Base	Modifier	
			Planning	Under	
Code	Description	Planning Unit	Value	Traffic	Urban
EARTHWORK		•			
01	Roadway Layout Staking	Roadway Mile	61	15	15
02	Cross Sectioning & Slope Staking	Roadway Mile	38	10	10
03	Grade Control Subgrade	Roadway Mile	50	10	10
0/	Bonoval and Dalagation Transation	Roadway Mile	71	10	10
04	Removal and Relocation Inspection	Roadway Mile	0	0	9
05	Earthwork Inspection	Roadway Mile	18	5	18
06	Density Earthwork & Drainage	Roadway Mile	30	0	30
07	Preparation for Const Office	Roadway Mile	20	0	20
08	Earthwork Office	Roadway Mile	40	0	0
DRAINAGE	······································				
11	Drainage Structure Staking	Roadway Mile	27	4	9
12	Drainage Structure Inspection	Roadway Mile	22	6	44
13	Drainage Structure Office	Roadway Mile	17	0	
14	Cost-in-Place Box Culuert Staking	Roadway Mile	17	0	4
14	Cast in Place Box Culvert Staking		12	2	4
15	Inspection	Each	35	9	9
16	Cast-in-Place Box Culvert Office	Each	11	0	0
ለሮሮ₽ፑሮለሞፑ			1		
AGGREGATE			0.0	-	•
21	Const/Paving	Roadway Mile	30	5	8
22	Aggregate Construction Inspection	1,000 Ton	6	0	2
23	Density Aggreg. Construction	Roadway Mile	12	0	12
24	Gradation Aggreg, Construction	1.000 Top		Ő	1
25	Weigh Aggregate Materials	1,000 Ton	6	0	1 2
2.5	Obach for Are Materials	1,000 1011	0	0	2
20	Uneck for Agg. Materials	1,000 Ton	6	0	2
27	Aggregate Construction Office	Roadway Mile	1	0	0
ASPHALT PAV	ING	······		*****	
31	Asphalt Paving Inspection	1 000 Tons	9	2	2
32(1)	Asphalt Plant Inspection	1,000 Tons	ó	2	2
32(1)	Noish (Obash Asshalt Min	1,000 Tons	10	2	2
33(1)	weigh/ check Asphalt Mix.	1,000 Tons	13	3	3
34	Asphalt Paving - Office	1,000 Tons	2	0	0
PCC PAVING		1 000			
41	Inspection	1,000 Sq. Yds.	6	2	2
42(1)	PCC Plant - Paving	1,000 Sg. Yds.	5	1	1
43	Joint Repair Inspection	100 Sa. Yds.	22	Ō	11
44	PCC Paving - Office	1,000 Sq. Yds.	1	Õ	0
STRUCTURE					
51	Structure Staking	Bent	5	1	0
52	Structure Inspection	Span-Lane	61	15	0
53(1)	PCC Plant Structure	Span-Lane	15	4	0
54	Structure Office	Span-Lane	20	0	0
MISCELLANEO	US		······		
61	Staking Misc. Items	Roadway Mile	23	6	8
62	Inspection for Misc. Items	Roadway Mile	26	. 7	13
63	Office Work for Miss Itoms	Roadway Mila	20	,	۰ ۲٦
0.0	ATTICE MOLY TOT MIDE. TESMS	Roadway Mile	U	U	0

3 1 • •

TABLE OF ACTIVITY PLANNING STANDARDS Contract Type - Widening & Resurfacing

			* Base	Modifier	
			Planning	Under	
Code	Description	Planning Unit	Value	Traffic	Urban
GENERAL					
81(2)	General Office Work	Insp. MH	15%		
82	Project Super. and Management	MH Act. 01-81	10%		
83	Standby	MH Act. 01-81	02%		
84(3)	Travel One Way				
	0 - 15 Min.	Staking & Insp.	МН 0%		
	20 - 45 Min.	Staking & Insp.	MH 15%		
1	More Than 45	Staking & Insp.	MH 25%		

* Manhours/Planning Unit

- (1) Central inspection activities (District 5 and 9 only) omit activities 32, 42, 53, and 50% of 33.
- (2) The Planning Unit for Activity Code 81 is the sum of the manhours required for Activity Codes 04, 05, 06, 12, 15, 22, 23, 24, 25, 26, 31, 32, 33, 41, 42, 43, 52, 53, and 62.
- (3) The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Codes 01, 02, 03, 11, 14, 21, 51, 61, plus the Planning Unit for Activity Code 81.

TABLE OF ACTIVITY PLANNING STANDARDS

Contract Type - Resurfacing

PI	LANNING ACTIVITY		* BASE	MOD	IFIER
CODE	DESCRIPTION	PLANNING UNIT	PLANNING VALUE	UNDER TRAFFIC	URBAN
AGGREGATE					
21	Line/Grade Control Agg. Const. Pvg.	Roadway Mile	16	. 2	4
22	Aggreg. Construction Insp.	1,000 Ton	9	0	2
23	Density Aggregate Construction	Roadway Mile	8	0	8
24	Gradation Aggregate Construction	1,000 Ton	2	0	2
25	Weigh Aggregate Materials	1,000 Ton	9	0	2
26	Checker for Agg. Materials	1,000 Ton	8	0	2
27	Aggregate Construction Office	Roadway Mile	1	0	0
ASPHALT PAV	VING			· · · · · · · · · · · · · · · · · · ·	•
31	Asphalt Paving Inspection	1,000 Tons	6	2	2
32(1)	Asphalt Plant Inspection	1,000 Tons	7	2	2
33(1)	Weigh/Check Asphalt Material	1,000 Tons	10	2	2
34	Asphalt Paving Office	1,000 Tons	2	0	0
PCC PAVING					
43	Joint Repair Inspection	100 Sq. Yds.	22	0	11
MISCELLANEC	DUS				
61	Staking for Miscellanous Items	Roadway Mile	8	0	4
62	Inspection for Miscellaneous Items	Roadway Mile	26	0	13
- 63	Office work for Miscellaneous Items	Roadway Mile	5	0	2
64	R/W Staking and Monumentation	Roadway Mile	. 60	0	60
65	Staking Turn Lanes	Turn Lane	8	0	. 8
66	Inspection for Turn Lanes	Turn Lane	7	0	7
67	Office Work for Turn Lanes	Turn Lane	3	0	0

TABLE OF ACTIVITY PLANNING STANDARDS

Contract Type - Resurfacing (Continued)

GENERAL 81(2) 82 83	General Office Work Project Supervision and Management Standby	Inspection MH MH Act. 01-81 MH Act. 01-81	10% 10% 02%
84(3)	Travel One Way 0 - 15 Min. 20 - 45 Min. More Than 45	Stkg. & Insp. MH Stkg. & Insp. MH Stkg. & Insp. MH	0% 15% 25%

* Manhours/Planning Unit

1 - 30

(1) Central inspection activities (Districts 5 and 9 only) omit activities 32, and 50% of 33.

(2) The Planning Unit for Activity Code 81 is the sum of the manhours required for Activity Codes 22,

23, 24, 25, 26, 31, 32, 33, 43, 62 and 66.

(3) The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Codes 21, 22, 23, 24, 25, 26, 31, 32, 33, 43, 61, 62, 64, 65 and 66.

TABLE OF ACTIVITY PLANNING STANDARDS

Contract Type - Bridge Repair

P	LANNING ACTIVITY		* BASE	MOD	IFIER
CODE	DESCRIPTION	PLANNING UNIT	PLANNING VALUE	UNDER TRAFFIC	URBAN
STRUCTURE					
51	Structure Staking	Span	10	10	0
52	Structure Inspection	Working Day	10	2	0
GENERAL					
81	General Office Work	Working Day	3	0	0
82	Project Supervision and Management	MH Act. 01-81	15%		
83	Standby	MH Act. 01-81	02%	4	
**84	Travel One Way				
	0 - 15 Min.	Stkg. & Insp. MH	0%		
	20 - 45 Min.	Stkg. & Insp. MH	15%		
	More Than 45	Stkg. & Insp. MH	25%		

* Manhours/Planning Unit

** The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Code 51 and 52.

TABLE OF ACTIVITY PLANNING STANDARDS

Contract Type - Intersection Improvements

	ΟΙ ΑΝΝΙΝΟ ΑΟΤΙΙΙΤΥ		* BASE	MOD	IFIER
CODE	DESCRIPTION	PLANNING UNIT	PLANNING VALUE	UNDER TRAFFIC	URBAN
MISCELLANE	Sous Staking Missellaneous Items	Working Day	8	3	0
62	Inspection of Miscellaneous Items	Working Day	15	0	4
GENERAL				0	0
81	General Office Work	Working Day	2	U	0
82	Project Supervision and Management	MH Act. 01-81	15%		
83	Standby	MH Act. 01-81	02%		
**84	Travel One Way 0 - 15 Min. 20 - 45 Min. More Than 45	Stkg. & Insp. MH Stkg. & Insp. MH Stkg. & Insp. MH	0% 15% 25%		

* Manhours/Planning Unit

1-32

** The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Code 61 and 62.

TABLE OF ACTIVITY PLANNING STANDARDS

Contract Type - Safety and Traffic Control

F	PLANNING ACTIVITY		* BASE	MOD	IFIER
CODE	DESCRIPTION	PLANNING UNIT	.PLANNING VALUE	UNDER TRAFFIC	URBAN
MISCELLANE	EOUS				
61	Staking Miscellaneous Items	Working Day	1	0	0
62	Inspection of Miscellaneous Items	Working Day	6	0	3
GENERAL			· · · ·		
81	General Office Work	Working Day	2	0	0
82	Project Supervision and Management	MH Act. 01-81	15%		
83	Standby	MH Act. 01-81	02%		
**84	Travel One Way				
	0 - 15 Min.	Stkg. & Insp. MH	0%		
	20 - 45 Min.	Stkg. & Insp. MH	15%		
	More Than 45	Stkg. & Insp. MH	25%		

* Manhours/Planning Unit

** The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Code 61 and 62.

TABLE OF ACTIVITY PLANNING STANDARDS

Contract Type - Miscellaneous

p	LANNING ACTIVITY		* BASE	MOD	IFIER
CODE	DESCRIPTION	PLANNING UNIT	PLANNING VALUE	UNDER TRAFFIC	URBAN
MISCELLANE	OUS				
61	Staking Miscellaneous Items	Working Day	1	0	0
62	Inspection of Miscellaneous Items	Working Day	9	0	0
GENERAL					
81	General Office Work	Working Day	2	0	0
82	Project Supervision and Management	MH Act. 01-81	15%		
83	Standby	MH Act. 01-81	02%		
**84	Travel One Way				
	0 - 15 Min.	Stkg. & Insp. MH	0%		
	20 - 45 Min.	Stkg. & Insp. MH	15%		
	More Than 45	Stkg. & Insp. MH	25%		

* Manhours/Planning Unit

** The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Code 61 and 62.

TABLE OF ACTIVITY PLANNING STANDARDS

Contract Type - Unique

P	PLANNING ACT	IVITY		* BASE	MOD	IFIER
CODE		DESCRIPTION	PLANNING UNIT	PLANNING VALUE	UNDER TRAFFIC	URBAN
MISCELLANE	COUS					
71	Special	Feature Staking	Lump Sum (Estimate)			
72	Special	Feature Inspection	Lump Sum (Estimate)			
73	Special	Feature Office	Lump Sum (Estimate)			
GENERAL			an na mar ann an an ann an ann ann ann ann ann			·····
81	General	Office Work	Lump Sum (Estimate)			
82	Project	Supervision and Management	Lump Sum (Estimate)			
83	Standby		MH Act. 01-81	02%		
**84	Travel	One Way				
		0 - 15 Min.	Stkg. & Insp. MH	0%		
		20 - 45 Min.	Stkg. & Insp. MH	15%		
		More Than 45	Stkg. & Insp. MH	25%		

* Manhours/Planning Unit

** The Planning Unit for Activity Code 84 is the sum of the manhours required for Activity Code 71 and 72.

PART THREE Scheduling

The third element of the Construction Engineering Manpower Management System is scheduling.

Manpower scheduling is essential for proper project management and promotes efficient use of assigned personnel.

Benefits derived from manpower scheduling include:

- Personnel excesses or deficiencies become apparent early.
- Engineers and Project Supervisors become more familiar with the Contractor's sequence of operations.
- Project personnel can be given secondary assignments for those times when the Contractor's work schedule is interrupted.
- Minimizes standby time and maximizes use of available personnel.
- Improves communication which inturn improves the supervisoremployee relationship.
- Facilitates the monitoring function, since the activity codes are shown on the scheduling form.

The Project Engineer is responsible for planning the manpower schedule. The Construction Project Manpower Schedule should be completed on Thursday of each week for the coming week. Each Resident Office should inform the District Office of manpower excesses or deficiencies that become apparent when planning the schedule. The Construction Project Manpower Schedule is only used at the project management level. A sample schedule is shown on page 3-2.

3-1

The scheduling function is not essential to the operation of the system and if it is not used will have very little effect on the information generated by the monitoring function. However, scheduling is a good management practice and it is recommended that it be used as much as possible. The scheduling system discussed in this section of the manual can be used as a guide.

PART FOUR Monitoring

The fourth element of the Construction Engineering Manpower Management System is monitoring.

Monitoring provides for evaluating work performance, staffing, construction progress, and for making staffing adjustments when necessary. It also provides data for upgrading the standard planning values.

Construction engineering performance on each contract should be monitored and controlled by the Project/Resident Engineer. The District will monitor manpower usage and work accomplishment through the Bi-Weekly Construction Project Manpower Report.

The first step in monitoring is the completion of the Bi-Weekly Construction Activity Report. This report is completed by each person working on a project. These reports should be kept current on a daily basis and turned in at the end of each pay roll period to the person in the Resident Office responsible for collecting this report. The field personnel using these reports should be given a copy of the Individual Planning Activity definitions (pages 1-8 to 1-16) and instructions for their use. A suggested handout is shown in Appendix C. A completed Bi-Weekly Construction Activity Report is shown on page 4-2. A list of the Activity Codes to be used on a project should be made available to all personnel working on that project so that only those Activities which were used on the Construction Project Manpower Planning Report are used for monitoring. A sample form to use for this purpose is shown on page C-3.

4-1

BI-WEEKLY CONSTRUCTION ACTIVITY REPORTS

Each employee involved in field or office work will complete this report each payroll period and submit it to the office with his time sheet. All time should be recorded to the nearest whole hour. As the Bi-Weekly Construction Activity Report is the first step in monitoring the manpower used on a project, it is important that it be filled out accurately and turned in on time. A sample of the completed report is shown below.

Note: A separate report should be filled out for each contract on which the employee has worked during the payroll period.

	В	I-W	EEK	LY	CON	STR	UCT	ION	AC	TIV	ITY	RE	POR	т	
S.P. 5508-38															
PAY PERIOD ENDING TUESDAY, May 22 , 19 79															
NAME John Q. Inspector															
CLASS TITLE Intermediate Highway Technician															
Intermediate Highway Technician ACTIVITY 9 10 11 12 13 14 15 16 17 18 19 20 21 22 CODE W T F S M T W T F S M T TOTAL															
52	4	7	3	6		5	8		1	4					.38
53	5	2						2	7		8		4	3	31
54	1		2			2		2		4					11
15			5	3		1		4	1				4	3	21
16				1		1		1						1	4

APPENDIX "C"

Examples of Computer Printouts

Reports printed by the Computer are 17 inches wide and are difficult to reproduce. Consequently, only examples of the computer printouts are shown in this appendix.

CONSTRUCTION PROJECT MANPOWER PLANNING REPORT Contract Type Construction Project Location & Description In Fillmore County, 3.8 miles S. of Spring Valley - Grading, Bit. Surface & Bridge

District 6 S.P. 2313-10 T.H. 53 Prop. Letting Date 2/24/78 Т.Н. 53 Date Prepared 3/1/78

			NUMBER	STANDARD		·····	
			OF X	PLANNING =	MAN-HOURS	MAN-HOURS	= FOUTVALENT
		PLANNING	PLANNING	VALUE	REQUIRED	DED	MAN-MONTUS
CODE	PLANNING ACTIVITY	UNIT	UNITS	(M-HRS/UNIT)	NDQ01NDD	MAN-MONTH	rian-rion 165
EARTHW	JORK	^		(11 11(0) 04(11)		HAN HONTH	
01	Roadway Layout Staking	Roadway Miles	1.0	127	127	173	0 7
02	Cross Sectioning & Slope Staking	Roadway Mile	1.0	68	68	173	0./
03	Grade Control Subgrade	Roadway Mile>	1.0	64	64	173	0.4
04	Removal & Relocation Inspection	Roadway Mile	1.0	17	17	217	0.4
05	Earthwork Inspection	10.000 SY RM	4.6	8	37	217	0.1
06	Density Earthwork & Drainage	Roadway Mile	1.0	25	25	217	0.1
07	Preparation for Constr Office	Noadway Mile	1.0	21	23	173	0.1
08	Earthwork Office	Roadway Mile	1.0	44	<u> </u>	173	0.2
	Total Earth Work Activities	V			····	1/5	1 2 2 1
DRAINA	GE						
11	Drainage Structure Staking	Roadway Mile	1.0	43	43	173	0.2
12	Drainage Structure Inspection	Roadway Mile	1.0	18	18	217	0.1
13	Drainage Structure POlice	Roadway Mile	1.0	11	11	173	0.1
14	C.I.P. Box Culvert Staking	Each	0	+ +		173	U•1
15	C.I.P. Box Quivert-Inspection	Each	0			217	
16	C.I.P. Box Culvert-Office	Each	0			173	
	Total Drainage Activities					175	0 / 1
AGGREG	ATE	······································			-		0.4
21	Line/Grade Control Aggregate						
	Construction/Paving	Roadway Mile	1.0	53	53	173	0.3
22	Aggregate Construction Inspection	1,000 Tons	1.0	44	<u> </u>	217	0.3
23	Density Aggreg. Construction	Roadway Mile	1.0	12	12	217	0.1
24	Gradation Aggreg. Construction	1.000 Tons	1.0	1	1	217	0.0
25	Weigh Aggregate Materials	1.000 Tons	0.0	5	<u>+</u>	217	0.0
26	Check for Aggregate Materials	1.000 Tons	0.0	5	0	217	0.0
27	Aggregate Construction Office	Roadway Mile	1.0	2	<u>0</u>	173	0.0
	Total Aggregate Activities					175	
ASPHAL	T PAVING				· · · · · · · · · · · · · · · · · · ·		0.0
31	Asphalt Paving Inspection	1,000 Tons	3.4	6	20	217	0.1
32	Asphalt Plant Inspection	1,000 Tons	3.4	7	20	217	0.1
33	Weigh Asphalt Mixture	1,000 Tons	3.4	10	34	217	0.1
34	Asphalt Paving Office	1,000 Tons	3.4	2	7	173	0.0
					· · · · · · · · · · · · · · · · · · ·	1/5	
	Total Asphalt Paying Activition						1

Total Asphalt Paving Activities

د_ k a

• (

- _

OF X PLANNING P MAN-HOURS / MAN-HOURS EQUITALENT CODE PLANNING ALANTING VALUE Required Required Required MAN-HOURS EQUITALENT CP AVENG UNIT UNITS (M-HRS/UNIT) MAN-HOURS EQUIVALENT 41 Portland Geneat Concrete				NUMBER	STANDARD			
PLANNING PLANNING VALUE REQUIRED PER MAN-MONTH 2020 PLANNING ACTIVITY UNIT UNIT UNITS (M-HRS/UNIT) MAN-MONTH 2021 Paving Inspection 1,000 S.Y. 0 217 217 42 PCC Plant — Paving 1,000 S.Y. 0 217 217 43 Joint Repair Inspection 1000 S.Y. 0 217 217 44 PCC Paving activities 173 0.3 217 0.3 51 Structure Staking Bent or Spink 2 22 44 173 0.3 52 Structure Inspection SpanChane 173 0.7 0.7 0.7 53 PCC Plant — Structure Activities Fund Lane 8 16 128 173 0.7 54 Structure - Office Spin Lane 8 16 128 173 0.1 61 Staking for Miscellaneous ICens Ruy Mi. or WD 1.0 30 30 217 <t< td=""><td></td><td></td><td></td><td>OF X</td><td>X PLANNING =</td><td>MAN-HOURS</td><td>/ MAN-HOURS :</td><td>= EQUIVALENT</td></t<>				OF X	X PLANNING =	MAN-HOURS	/ MAN-HOURS :	= EQUIVALENT
DODE PLANNICA CTIVITY UNIT UNITS (M-HRS/UNIT) MAN-MONTH 41 Portland Cement Concrete 217 217 217 42 PCC Plant Paving 1,000 S.V. 0 217 43 Joint Repair Inspection 100 S.V. 0 217 44 PCC Plant Paving 1,000 S.V. 0 217 44 PCC Plant Paving 1,000 S.V. 0 217 44 PCC Plant Paving 1,000 S.V. 0 217 44 PCC Paving Office 1,000 S.V. 0 173 0.3 Structure Staking Bent or Spark 2 22 44 173 0.3 51 Structure Staking Bent or Spark 2 22 44 173 0.5 54 Structure - Office Spart Lane 8 16 128 173 0.7 Total Structure Activities Probat Lane 8 16 128 173 0.1 61 Sta			PLANNING	PLANNING	VALUE	REQUIRED	PER	MAN-MONTHS
CC PAVING 1 Portland Cement Concrete Paving Inspection 1,000 S.Y. 0 217 42 PCC Plant Paving 1,000 S.Y. 0 217 43 Joint Repair Inspection 100 S.Y. 0 217 44 PCC Paving Office 1,000 S.Y. 0 217 Total PCC Paving Activities 1,000 S.Y. 0 173 Total PCC Paving Activities 1,000 S.Y. 0 173 Total PCC Paving Activities Span Dame 173 0.3 52 Structure Staking Bent or Span 2 22 44 173 0.3 53 Structure Office Span Dame 8 16 128 173 0.7 54 Structure Office Span Dame 8 16 128 173 0.7 55 Structure Office Rday Mi. or WD 1.0 23 23 173 0.1 61 Staking for Miscellageous Hems Rdway Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and MonumentarDan Roadw	CODE	PLANNING ACTIVITY	UNIT	UNITS	(M-HRS/UNIT)	•	MAN-MONTH	
41 Portland Coment Concrete 1,000 S.Y. 0 217 42 PCC Plant Paving 1,000 S.Y. 0 217 43 Joint Repair Inspection 100 S.Y. 0 217 44 PCC Plant Paving 100 S.Y. 0 217 44 PCC Paving Activities 173 173 Total PCC Paving Activities 173 0.3 51 Structure Staking Bent or Span 2 22 44 173 0.3 52 Structure Inspection Span Lane 8 11 88 173 0.5 54 Structure - Office Total Structure Activities 4.2 4.2 ISCELLAMCOUS 4.2 10 1.0 23 23 173 0.1 61 Staking for Miscellaneous Remay Mi. or WD 1.0 30 30 217 0.1 62 Inspection for Miscellaneous Activities 173 61 173 63 0.2 64 173 0.2 61 Staking furn Lanes 173 173 173	PCC PA	AVING						
Paving Inspection 1,000 S.Y. 0 217 42 PCC Plant Paving 1,000 S.Y. 0 217 43 Joint Repair Inspection 100 S.Y. 0 217 44 PCC Paving Office 1,000 S.Y. 0 217 44 PCC Paving Activities 1 1 1 Total PCC Paving Activities 1,000 S.Y. 0 173 1 Total PCC Paving Activities 1 0.3 3 1 0.3 51 Structure Staking Bent or Span 2 22 44 173 0.3 52 Structure Inspection Span Lane 8 11 88 173 0.5 54 Structure Activities 1 4.2 173 0.1 1.0 23 23 173 0.1 61 Staking for Miscellaneous Hems Rdwy Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumentarizon Rodwy Mii. or WD 1.0 34 34	41	Portland Cement Concrete						
42 PCC Plant - Paving 1,000 S.Y. 0 217 43 Joint Repair Inspection 100 S.Y. 0 217 44 PCC Paving Office 1,000 S.Y. 0 173 Total PCC Paving Activities 1 1 1 1 Structure Staking Bent or Sphn 2 22 44 173 0.3 51 Structure Inspection Span Dame 8 58 464 2.7 53 PCC Plant Structure Span Dame 8 18 11 88 173 0.5 54 Structure Office Span Lane 8 16 128 173 0.7 Total Structure Office Span Lane 8 16 128 173 0.1 62 Inspection for Miscellaneous Remay Mi. or WD 1.0 23 23 173 0.1 63 Office Work for Miscellaneous Remay Mi. or WD 1.0 34 173 0.2 64 R/W Staking and Monumentation Rodaway Mi. or WD 1.0 34 173 0.2 65		Paving Inspection	1.000 S.Y.	0			217	
43 Joint Repair Inspection 100 S.Y. 0 217 44 PCC Paving - Office 1,000 S.Y. 0 173 TAUCTURE 173 173 173 Structure Staking Bent or Span 2 22 44 173 0.3 51 Structure Inspection Span Dame 8 58 464 2.7 53 Structure Inspection Span Dame 8 11 86 173 0.5 54 Structure - Office Apail Lane 8 16 128 173 0.7 Total Structure Activities VM 8 58 464 2.7 4.2 Staking for Miscellaneous Items Riwy Mi. or WD 1.0 23 23 173 0.1 62 Inspection for Miscellaneous Items Riwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Relway Mi. or WD 1.0 34 173 0.2 64 R/W Staking and Monumentation Roadway Mile 173 173 0.2 65	42	PCC Plant Paving	1.000 S.Y.	0			217	
44 PCC Paving Office 1,000 S.Y. 0 173 Total PCC Paving Activities Total PCC Paving Activities Total PCC Paving Activities Structure Staking Bent or Span 2 22 44 173 0.3 Structure Staking Bent or Span 2 22 44 173 0.3 Structure Inspection Span Dane 8 58 464 2.7 Structure - Office Span Dane 8 188 173 0.5 Structure - Office Span Dane 8 16 128 173 0.1 Structure - Office Advery Mi. or WD 1.0 23 23 173 0.1 GI Inspection for Miscellaneous Rems Rdway Mi. or WD 1.0 34 34 173 0.2 GI Inspection for Miscellaneous Activities Itrue Lanes 173 GI Inspection for Miscellaneous Activities 173 Office Work for Tiscellaneous Activities 173 <td>43</td> <td>Joint Repair Inspection</td> <td>100 S.Y.</td> <td>0</td> <td></td> <td></td> <td>217</td> <td></td>	43	Joint Repair Inspection	100 S.Y.	0			217	
Total PCC Paving Activities Image: Construct of the second s	44	PCC Paving Office	1.000 S.Y.	0			173	
TRUCTURE Bent or Span 2 22 44 173 0.3 51 Structure Inspection Span Dame 8 58 464 2.7 53 PCC Plant Structure Span Dame 8 11 88 11 0.5 54 Structure Office Span Lane 8 11 88 173 0.7 Total Structure Activities Proba Lane 8 16 128 173 0.1 61 Staking for Miscellaneous Items Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Items Rdwy Mi. or WD 1.0 30 30 217 0.1 64 R/W Staking and Monumentation Roadway Mile 173 0.2 64 173 0.2 65 Staking Turn Lanes 173 1.0 34 173 0.2 61 Inspection for Turp Lanes 173 173 0.2 173 70 Office Work for Turp Lanes 173 173 0.4 173 71 Special Fea		Total PCC Paving Activities		••••••••••••••••••••••••••••••••••••••				
51 Structure Staking Bent or Span, 2 22 44 173 0.3 52 Structure Inspection Span Dane 173 173 53 PCC Plant Structure Span Dane 8 58 464 2.7 53 PCC Plant Structure Span Lane 8 11 88 173 0.5 54 Structure - Office Span Lane 8 16 128 173 0.7 Total Structure Activities Rdwy Mi. or WD 1.0 23 23 173 0.1 61 Staking for Miscellaneous Items Rdwy Mi. or WD 1.0 30 30 217 0.1 62 Inspection for Misc. Items Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Mems Rdwy Mi. OWD 1.0 30 30 217 0.1 64 R/W Staking and Monumentelon Roadway Mi. No WD 1.0 30 30 217 0.1 65 Staking Turn Lanes 173 173 0.4 173 0	STRUCT	CURE CURE	\sim	<u>۲</u>				l
52 Structure Inspection Spar Lane 173 173 53 PCC Plant Structure Spar Lane 8 11 88 173 0.5 54 Structure Office Spar Lane 8 11 88 173 0.5 54 Structure Office Spar Lane 8 11 88 173 0.7 Total Structure Activities Par Lane 8 16 128 173 0.7 1SCELLANGOUS Issection for Miscellaneous Items Rdwy Mi. or WD 1.0 23 23 173 0.1 61 Staking Turn Lanes Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Leems Rdway Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking Turn Lanes Turn Lanes 173 173 173 173 65 Isage Laneous Activities Turn Lanes 173 173 173 173 66 Inspection for Turn Lanes Turn Lanes 173 173 173 173 127 173<	51	Structure Staking	Bent or Span	2	22	44	173	0.3
S3 PCC Plant Structure Span Lane 8 11 88 173 0.5 53 Structure Office Span Lane 8 11 88 173 0.5 Total Structure Activities Span Lane 8 16 128 173 0.7 SisceLLANEOUS 1.0 23 23 173 0.1 61 Staking for Miscellaneous Items Rdwy Mi. or WD 1.0 30 30 217 0.1 62 Inspection for Misc. Items Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Items Rdwy Mi. or WD 1.0 34 34 173 64 R/W Staking and Monumentation Roadway Mile 173 173 0.2 65 Staking Turn Lanes Turn Lanes 173 173 0.2 67 Office Work for Ture Inspection Lump Sum Est. 217 173 73 Special Feature Inspection Lump Sum Est. <td>52</td> <td>Structure Inspection</td> <td>Span Lane</td> <td></td> <td></td> <td></td> <td>173</td> <td></td>	52	Structure Inspection	Span Lane				173	
53 FCC Plant Structure Span Lane 8 11 88 173 0.5 54 Structure Office Span Lane 8 16 128 173 0.7 Total Structure Activities Image: Structure Activities 4.2 ISCELLANEOUS Rdwy Mi. or WD 1.0 23 23 173 0.1 61 Staking for Miscellaneous Items Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Items Rdwy Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumentation Roadway Mile 173 0.2 173 0.2 65 Staking Turn Lanes 173 173 0.2 173 0.2 66 Inspection for Turp Lanes 173 173 0.4 173 0.4 70 Special Feature Staking Lump Sum Est. 173 0.4 71 Special Feature Staking Lump Sum Est. 173 0.7 72 Special Feature Staking Lump Sum Es			er WD	8	58	464		2.7
54 Structure Office Structure Activities 0.7 Total Structure Activities 0.7 4.2 SCELLANEOUS 1.0 23 23 173 0.1 61 Staking for Miscellaneous Items Rdwy Mi. or WD 1.0 30 30 217 0.1 62 Inspection for Misc. Items Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Items Rdwy Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumelation Rodway Mile 173 0.2 173 0.1 65 Staking Turn Lanes 173 173 0.2 173 0.2 66 Inspection for Turn Lanes 173 173 0.2 173 67 Office Work for Turn Lanes 173 0.4 173 0.4 70 Special Feature Staking Lump Sum Est. 173 0.4 71 Special Feature - Office Lump Sum Est. 173 0.7 73 Special Feature - Office	53	PCC Plant Structure	/Span Lane	8	11	88	173	0.5
Total Structure Activities 4.2 ISCELLANEOUS 1.0 23 23 173 0.1 61 Staking for Miscellaneous Kems Rdwy Mi. or WD 1.0 30 30 217 0.1 62 Inspection for Miscellaneous Items Rdway Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Items Rdway Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumentation Rodawy Mile 173 0.2 173 0.2 65 Staking Turn Lanes 173 173 0.2 173 0.1 66 Inspection for Turn Lanes 173 173 0.2 173 173 67 Office Work for Turn Lanes 173 0.4 173 0.4 173 70 tal special Feature Staking Lump Sum Est. 173 0.4 173 72 Special Feature Inspection Lump Sum Est. 173 173 173 70 tal Spec. Featu	54	Structure Office	Span Lane	8	16	128	173	0.7
ISCELLANEOUS 1 23 23 173 0.1 61 Staking for Miscellaneous Lems Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Lems Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Lems Rdwy Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumendation Roadway Mile 173 0.1 0.1 65 Staking Turn Lanes 173 0.1 0.2 0.1 0.2 66 Inspection for Tuch Lengs Turn Lanes 173 0.1 0.4 70 Office Work for Turn Lengs Turn Lanes 173 0.4 70 Special Feature Staking Lump Sum Est. 173 0.4 71 Special Feature Inspection Lump Sum Est. 173 0.4 71 Special Feature Inspection Lump Sum Est. 173 0.4 72 Special Feature Activities 173 0.4 173 0.7 <td></td> <td>Total Structure Activities</td> <td>$\overline{\langle \rangle}$</td> <td></td> <td></td> <td></td> <td></td> <td>4.2</td>		Total Structure Activities	$\overline{\langle \rangle}$					4.2
61 Staking for Miscellaneous Kams Rdwy Mi. or WD 1.0 23 23 173 0.1 62 Inspection for Misc. Items Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous Hems Rdway Mi. or WD 1.0 34 34 173 0.2 63 Office Work for Miscellaneous Hems Rdway Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumentation Rodway Mile 173 0.2 65 Staking Turn Lanes 173 173 0.2 66 Inspection for Turn Lanes 173 173 0.4 67 Office Work for Turn Lanes 173 0.4 0.4 70 Special Feature Staking Lump Sum Est. 173 0.4 71 Special Feature Inspection Lump Sum Est. 217 0.4 73 Special Feature Activities WD 1.0 34 1.0 0.4 81 General Office Work MH Insp. Act, WD 1.0 0.7 82 <td>MISCEL</td> <td>LLANEOUS</td> <td></td> <td></td> <td></td> <td></td> <td>· · · · · · · · · · · · · · · · · · ·</td> <td></td>	MISCEL	LLANEOUS					· · · · · · · · · · · · · · · · · · ·	
62 Inspection for Misc. Items Rdwy Mi. or WD 1.0 30 30 217 0.1 63 Office Work for Miscellaneous 20 mm Roadway Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumentation Roadway Mile 173 0.2 64 R/W Staking and Monumentation Roadway Mile 173 0.2 65 Staking Turn Lanes 173 173 66 Inspection for Turn Lanes 173 173 67 Office Work for Turn Lanes 173 701 Special Feature Staking Lump Sum Est. 173 71 Special Feature Staking Lump Sum Est. 173 72 Special Feature Staking Lump Sum Est. 173 73 Special Feature Activities ND 1.0 173 0.4 73 Special Feature Activities ND 1.0 173 0.7 73 Special Feature Activities ND 1.0 1605 10 XMH 161 173 0.7 81 General Office Work M	61	Staking for Miscellaneous Items	Rawy Mi. or WD	1.0	23	23	173	0.1
63 Office Work for Miscellaneous Ytems Rdway Mi. or WD 1.0 34 34 173 0.2 64 R/W Staking and Monumentation Roadway Mile 173 173 65 Staking Turn Lanes 173 173 173 66 Inspection for Turh Lenes 173 173 67 Office Work for Turn Lanes 173 173 67 Office Work for Turn Lanes 173 0.4 70 Total Miscellaneous Activities 0.4 0.4 PECIAL FEATURES 173 0.4 71 Special Feature Staking Lump Sum Est. 217 72 Special Feature Inspection Lump Sum Est. 173 73 Special Feature - Office Lump Sum Est. 173 73 Special Feature - Office Lump Sum 814 15 XMH 122 173 0.7 74 Speci Features Activities 173 0.9 173 0.9 173 0.9 81 General Office Work MH Insp. Act, WD L. Sum 814 15 XMH 122 173	62	Inspection for Misc. Items	Rdwy Mi. or WD	1.0	30	30	217	0,1
64 R/W Staking and Monumentation Roadway Mile 173 65 Staking Turn Lanes 173 66 Inspection for Turn Lanes 173 66 Inspection for Turn Lanes 173 67 Office Work for Turn Lanes 173 70 Total Miscellaneous Activities 173 71 Special Feature Staking Lump Sum Est. 71 Special Feature Inspection Lump Sum Est. 71 Special Feature - Office Lump Sum Est. 73 Special Feature - Office Lump Sum Est. 74 Special Feature Activities 173 75 Special Feature - Office Lump Sum Est. 76 Office Work MH Insp. Act, 173 75 Supervision & Management MH Act.01-81 1605 10 % MH 161 173 0.7 81 General Activities 1236 15 % MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 % MH 32 173 0.2 <t< td=""><td>63</td><td>Office Work for Miscellaneous ILe</td><td>ems Rdway Mi. or V</td><td>ND 1.0</td><td>34</td><td>34</td><td>173</td><td>0.2</td></t<>	63	Office Work for Miscellaneous ILe	ems Rdway Mi. or V	ND 1.0	34	34	173	0.2
65 Staking Turn Lanes 173 66 Inspection for Turn Lanes 173 67 Office Work for Turn Lanes 173 70 Special Feature Staking Lump Sum Est. 71 Special Feature Inspection Lump Sum Est. 73 Special Feature - Office Lump Sum Est. 70 Special Feature - Office Lump Sum Est. 70 Special Feature - Activities 173 71 Standop MH Insp. Act, WD L. Sum 814 81 General Office Work MH Act.01-81 1605 10 %MH 161 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 <	64	R/W Staking and Monumentation	Roadway Mile				173	
66 Inspection for Tuth Longs Turn Lanes 173 67 Office Work for Turn Lanes 173 Total Miscellaneous Activities 0.4 PECIAL FEATURES 0.4 71 Special Feature Staking Lump Sum 72 Special Feature Inspection Lump Sum Est. 73 Special Feature Office Lump Sum Est. 217 73 Special Feature Office Lump Sum Est. 173 73 Special Feature Office Lump Sum Est. 217 73 Special Feature Office Lump Sum Est. 173 73 Special Feature Office Lump Sum Est. 173 73 Special Feature Activities 173 173 SteraL Read 173 173 173 81 General Office Work MH Insp. Act, WD L. Sum 814 15 %MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.2 84 Travel MH	65	Staking Turn Lanes	Turn Lanes			<u> </u>	173	
67 Office Work for Turn Lanes 173 Total Miscellaneous Activities 0.4 PECIAL FEATURES 173 71 Special Feature Staking Lump Sum 72 Special Feature Inspection Lump Sum 73 Special Feature Office Lump Sum 73 Special Feature Office Lump Sum 74 Special Feature Office Lump Sum 75 Special Feature Office Lump Sum 74 Special Feature Office Lump Sum 75 Special Feature Office Lump Sum 76 Special Feature Office Lump Sum 77 Special Feature Office Lump Sum 77 Special Feature Office Lump Sum 77 Special Feature Office Lump Sum 81 General Office Work MH Insp. Act, WD L. Sum 814 15 %MH 122 81 General Office Work MH Act.01-81 1605 2 %MH 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84	66	Inspection for Turn Lanes	Turn Lanes				173	
Total Miscellaneous Activities0.4PECIAL FEATURES71Special Feature StakingLump SumEst.17372Special Feature InspectionLump SumEst.21773Special Feature OfficeLump SumEst.17373Special Feature OfficeLump SumEst.17373Special Feature OfficeLump SumEst.17374Special Feature OfficeLump SumEst.17375Special Feature OfficeLump SumEst.17370Special Spec. Features ActivitiesWDL. Sum81415 %MH81General Office WorkMH Insp. Act, WD L. Sum81415 %MH16182Project Supervision & ManagementMH Act.01-81160510 %MH16183StandbyMH Act.01-8116052 %MH321730.284TravelMH Stkg.&Insp.123615 %MH1851731.1Total General ActivitiesPrepared byPrepared by	67	Office Work for Turn Lanes	Turn Lanes				173	
PECIAL FEATURES 173 71 Special Feature Staking Lump Sum Est. 217 73 Special Feature Inspection Lump Sum Est. 217 73 Special Feature Office Lump Sum Est. 217 73 Special Feature Office Lump Sum Est. 173 Total Spec. Features Activities Image: Special Feature Office Image: Special Feature Office Image: Special Feature Office 81 General Office Work MH Insp. Act, Image: Special Feature Office Image: Special Feature Office <td></td> <td>Total Miscellaneous Activities</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0.4</td>		Total Miscellaneous Activities						0.4
71 Special Feature Staking Lump Sum Est. 173 72 Special Feature Inspection Lump Sum Est. 217 73 Special Feature Office Lump Sum Est. 173 73 Special Feature Office Lump Sum Est. 173 70 Total Spec. Features Activities 173 173 ENERAL 81 General Office Work MH Insp. Act,	SPECIA	L FEATURES						
72 Special Feature Inspection Lump Sum Est. 217 73 Special Feature Office Lump Sum Est. 173 Total Spec. Features Activities Imp Sum Est. 173 ENERAL 81 General Office Work MH Insp. Act, WD L. Sum 814 15 %MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.9 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Prepared by	71	Special Feature Staking	Lump Sum	Est.			173	
73 Special Feature Office Lump Sum Est. 173 Total Spec. Features Activities Intervention Intervention Intervention 81 General Office Work MH Insp. Act, WD L. Sum 814 15 %MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.9 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Prepared by	72	Special Feature Inspection	Lump Sum	Est.	<u></u>		217	
Total Spec. Features Activities Total Spec. Features Activities ENERAL 81 General Office Work MH Insp. Act, WD L. Sum 814 15 %MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.9 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Prepared by	73	Special Feature Office	Lump Sum	Est.		······································	173	
ENERAL 81 General Office Work MH Insp. Act, WD L. Sum 814 15 %MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.9 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Prepared by		Total Spec. Features Activities	•					
81 General Office Work MH Insp. Act, WD L. Sum 814 15 %MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.9 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Prepared by	GENERA	AL						
WD L. Sum 814 15 %MH 122 173 0.7 82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.9 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Total Project Activities 2.9 Prepared by	81	General Office Work	MH Insp. Act.					
82 Project Supervision & Management MH Act.01-81 1605 10 %MH 161 173 0.9 83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Project Activities Prepared by			WD L. Sum	814	15 %MH	122	173	0.7
83 Standby MH Act.01-81 1605 2 %MH 32 173 0.2 84 Travel MH Stkg.&Insp. 1236 15 %MH 185 173 1.1 Total General Activities Total Project Activities Prepared by	82	Project Supervision & Management	MH Act.01-81	1605	10 %MH	161	173	0.9
84 Travel MH Stkg.&Insp. 1236 15 % MH 185 173 1.1 Total General Activities 2.9 2.9 11.2 11.2 Prepared by	83	Standby	MH Act.01-81	1605	2 %MH	32	173	0.2
Total General Activities 2.9 Total Project Activities 11.2 Prepared by	84	Travel	MH Stkg.&Insp.	1236	15 %MH	185	173	1.1
Total Project Activities 11.2		Total General Activities	·····					2.9
Prepared by		Total Project Activities						11.2
Prepared by								
riepated by			, ,		Dron	ared by		
					rrep			

1 - ₹9

ANNUAL CONSTRUCTION PROJECT STAFFING PLAN

District S.P. 2313-10 T.H. 63 Prop. Letting Date 2/24/78 Est.Comp.Date 10/30/78 Date Prepared 3/1/78 Planning Year 1978

PROJECT LOCATION

DESCRIPTION _____

2-4

	1	Dian	ManaMa	Man	t													1
		Fian	Man-MO.	man-						Man-	Month	IS	·				Cur.	Bal.
Code	Planning Astivity	Equiv.	usea lo	months	~					_	1			Į			Year	to
01	Pdry Longut Stabies	Man-Mo	Date	Remain	Jan	Feb	Mar	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	_Est.	Compl.
$\frac{01}{02}$	Xdwy. Layout Staking	0./	0	<u>(.</u>)/	5				0.2	0.2	0.1	0.1	0.0	0.1			0.7	0
02	A-Sec. & Slope Staking	0.4	0	0.4	\leq				0.2	0.2	<u> </u>						0.4	0
$\frac{0.5}{0.4}$	Grade Control-Subgrade	0.4		$0.4 \vee$						0.2			0.2				0.4	0
04	Removal & Rel.Insp.	0.1	0	Q.2						0.1							0.1	0
05	Earthwork Inspection	0.2	6	0.2						0.1		0.1					0.2	0
06	Density-Earth.&Drainage	0.1	$\mathcal{C}\mathcal{Q}$	0.1						0.1							0.1	0
07	Prep.for ConstOffice	0.1	2	0.1					0.1								0.1	0
08	Earthwork-Office	0.3	$0 \vee$	0.3						0.1	0.1	0.1					0.3	0
		\sim	$\overline{}$															
11	Drainage Struct.Staking	0.2	۱ŏ (0.2	{	· · ·		{	(0.2						[0.2	0
12	Drainage Struct.Insp	Q.N	0	0.1							0.1					}	0.1	0
13	Drainage Struct. Office	Q.2	0	0.1										0 1			0.1	0
14	Box Culvert-Steking																	0
15	Box Culvert-Inspection															{		<u> </u>
16	Box Culvert-Office					{							{					
	8																	
21	Line/Grade Control-Agg.	0.3	0	0.3								0.1	0.2	ł			0.3	0
22	Aggregate Const. Insp.	0.2	0	0.2								0.1	0.1				0.2	0
23	Density-Aggreg.Const.	0.1	0	0.1									0.1				0 10	
24	Gradation-Aggreg.Const.																-0.10	
25	Weigh Aggregate Mat'1.																	
26	Check/Aggreg. Mat'l.												}					
27	Aggregate ConstOffice																	
				}							ł		- [1				
l	La ser a		L	1			1					f	•	- (1	

• _

τ

		Plan	Man-Mo.	Man-	Man-Months									Cur.	Bal. ~			
		Equiv.	Used To	Months													Year	to
Code	Planning Activity	Man-Mo	Date	Remain	Jan	Feb	Mar	Apr	May	June	July	Aug	Sept	Oct	Nov	Dec	Est.	Compl.
31	Asphalt Paving Insp.	0.1	0	0.1									0.1				0.1	0
32	Asphalt Plant Insp.	0.1	0	0.1									0.1				0.1	0
33	Weigh Asphalt Mixture	0.2	0	0.2									0.2				0.2	0
34	Asphalt Paving-Office																	
41	Portland Cem.Conc.Pav.																	
42	PCC Plant-Paving																	
43	Joint Repair Inspec.		\neg															
44	PCC Paving-Office		AA.															
51		0.0	$\sum \langle q \rangle$	> 														
50	Structure Staking	0.3		0.3						$\frac{0.1}{1000000000000000000000000000000000$	0.1	0.1					0.3	0
52	Structure Inspection	2.		2.1						$\frac{1.0}{0.0}$	1.0	0.1					2.7	0
23	PCC Plant-Structure	0.2		0.5						0.2	0.2	0.1					0.5	0
54	Structure-Office	and)	<u> </u>	0./						0.1	0.1	0.2	0.3				0.7	0
61	Staking for Misc.Items	0.1	0	0.1													0	0.1
62	Insp. for Misc. Items	$\overline{0.Y}$	0	0.1													0	0.1
63	Office Work for Misc. Tr	Q.2	0	0.2													0	0.2
64	R/W Stak.& Monument																	
65	Staking Turn Lanes																	
66	Inspection/Turn Lanes						<u> </u>											
67	Office Work/Turn Lanes																	
71	Sanai di Catalana Stalina																	
$\frac{71}{72}$	Special Feature Staking						{							{				
73	Special Feature Insp.						{						{	{		{		
	Special reactile Office																	<u> </u>
81	General Office Work	0.7	0	0.7						0.1	0.1	0.1	0.1	0.2			0.6	0.1
82	Project Superv.&Manage.	0.9	0	0.9					0.1	0.1	0.2	0.1	0.1	0.1			0.7	0.2
83	Standby	0.2	0	0.2								0.1	0.1				0.2	0
84	Travel	1.1	0	1.1		{			0.1	0.2	0.2	0.2	0.2	0.1			1.0	0.1
85	Training & Equip.Maint.	0.1 .	0	0.1										0.1			0.1	
	Total Project Act.	11.0	0	11.0					0.7	3.0	2.2	2.1	1.8	0.7			10.5	0.8

2 - 5

Original - A.D.E. Copy - Project File

Dist	rict	6
Year	197	9
Date	Prepared	1/3/79

·

				MAN-M	ONTH			D	ISTRI	BUTIO	N	1
S.P. NUMBER	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JÜLY	AUG.	SEP.	OCT.	NOV.	DEC.
2313-10					0.7	3.0	2.2	2.1	1.8	0.7		
5508-28	0.4	0.2	0.2	0.6	0.9	1.3	0.3	0.0	0.0	0.0	0.0	0.0
2001-10	0.2	0.3	0.2	5.1	4.2	4.0	3.2	3.4	4.5	2.9	1.2	0.7
2510-9103	0	0	0	0	0.5	1.3	2.4	2.4	1.1	1.2	0.6	0.3
5507-24	0.5	0.4	0.9	2.1	4.3	5.1	6.0	5.8	5.8	5.2	4.0	2.1
5507-25	0.3	0.0	0.0	0.2	0.5	0.9	0.9	0.3	0.2	0.1	0.0	0.0
5510-42	0.0	0.2	0.3	0.3	0.9	1.0	1.0	1.0	1.0	1.0	0.7	0.2
5507-10	2.1	2.1	2.1	3.2	4.0	6,1	5.5	7.2	7.9	7.8	5.1	1.6
					\leq	Ž						
				\sum		\searrow						
			\sqrt{c}	\mathcal{D}	\mathbf{Y}							
				Š								
	$\langle \rangle$	1/1	\sim									
17	\geq	<u>بر</u>										
\sum												
)												
										•		
TOTAL PROJECT ACTIVITIES	3.5	3.2	3.7	11.5	16.0	22.7	21.5	22.2	22.3	18.9	11.6	4.9
% LEAVE & HOLIDAY	20.9	21.0	17.9	21.6	12.4	13.7	14.5	13.0	14.7	18.7	19.5	39.0
LEAVE & HOLIDAY MAN-MOS.	0.7	0.7	0.6	2.5	2.5	3.1	3.1	3.0	3.3	3.4	2.1	1.9
TOTAL REQ'D.MAN-MOS.	4.2	3.9	4.3	14.0	18.5	25.8	24.6	25.2	25.6	22.3	13.7	6.8
AVAILABLE MAN-MOS.	20	20	20	20	20	20	20	20	20	20	20	20
EXCESS OR DEFICIENCY	+ 15.8	+ 16.1	+ 15.7	+6.0	+1.5	5.8	-4.6	-5.2	-5.6	-2.3	+6.3	+ 13.2

Copy - District File

, ¥

י ג

CONSTRUCTION PROJECT MANPOWER SCHEDULE

For the Week Beginning May 14, 1979

S.P. 2313-10

• ...

		PRIMARY ASSIG	NMENT									SECONDARY	ΔSSICNMENT
	ACTIVITY	Remarks, Location	Name	1	H	OUF	2S						Remarks Location
Code	Title	Spec.Inst.,Etc.	Starting Time	s	M	T	Ĭw	T	F	l s	Code	Title	Spec. Equip. Etc.
	Earthwork					<u> </u>	<u> </u>	1-	1			Final quantities	Culverts at 2+00
5	Inspection	Entire Project	Randy H. 7:00		10	10		s 10	1 10	10	13	RecomputeBedding	3+50.4+10.8+50
6	Density	Entire Project	Randy H. 7:00					5					
3	Subgrade B.T.s	SBL 1+00 to 28+00	Glenn P , 7:00		8			8	*		02	X-Section	
1	Grade - Paving	SBL 0+00 to 28+00	Glenn P. 7:00			8		8	6			Borrow Pit	
3	Subgrade B.T.s	SBL 1+00 to 28+00	Carl S. 7:00		8			8			02	Borrow Pit	
1	Grade - Paving	SBL 0+00 to 28+00	Carl S. 7:00			8		8	8				
3	Subgrade B.T.s	SBL 1+00 10 28+00	Steve S. 7:00		8			8	×		02	Borrow Pit	
1	Grade - Paving	SBL 0+00 to 28+00	Steve S. 7:00			8	8	3	8				
12	Drainage Insp.)	Entire Project	Roger B. 7:00		5	5		5_5	5	5	13	Work with Randy	Above
15	C.I.P. Box Culv.	SBL 49+50	Roger B. 7:00		5	5		5 5	5	5			
53	Ready Mix Plant	Bridge 9069, 9033	Robert P. 7:00			4			4		52	Structure Insp.	Br. 9069,9033
52	Structure Insp.	Bridge 9069, 9033	Jim E. 7:00		10	10	10	10	10		54	Structure Office	Finals Br. 9069
52	Structure Insp.	Bridge 9069, 9033	Karl A. 7:00		10	10	10	10	10		54	Structure Office	Finals Br. 9069
								<u> </u>					
													· ·

3-2

.

BI-WEEKLY CONSTRUCTION PROJECT MANPOWER REPORT

Report No. S.P. Period Ending

ŧ.

PROJECT LOCATION AND DESCRIPTION

4-6

		MANHOURS					
			USED TO		PERCENT	REMARKS*	
CODE	PLANNING ACTIVITY	PLANNED	DATE	REMAINING	USED		
EARTHWO	RK						
01	Roadway Layout Staking	127	138	-11	109		
02	Cross Sectioning & Slope Staking	68	52	16	76		
03	Grade Control Subgrade	64	70	- 6	109		
04	Removal & Relocation Inspection	17	15	2	88		
05	Earthwork Inspection	37	60	-23	162	Contr.moving borrow with 2TS14 Scraper	
06	Density Earthwork & Drainage	25	25	0	100	· · · · · · · · · · · · · · · · · · ·	
07	Preparation for Construction-Office	21	20	1	95		
08	Earthwork Office	44	35	9	80		
DRAINAG	E						
11	Drainage Structure Staking	43	25	18	58		
12	Drainage Structure Laspection	18	20	- 2	111		
13	Drainage Structure Office	11	8	3	73		
14	C.I.P. Box Culvert Staking	0					
15	C.I.P. Box Culvert-Inspection	0					
16	C.I.P. Box Culvert-Office	0					
AGGREGA	TE						
21	Line/Grade Control Aggregate						
	Construction/Paving	53	62	- 9	117		
22	Aggregate Construction Inspection	44	35	9	18	All aggregate placed in one day	
23	Density Aggreg. Construction	20	30	-10	150	Had gradation problems	
24	Gradation Aggreg. Construction						
25	Weigh Aggregate Materials						
26	Check for Aggregate Materials						
27	Aggregate Construction Office	2	6	- 4	300		
ASPHALT	PAVING	· · ·				Contr. did not have enough trucks	
31	Asphalt Paving Inspection	20	36	-16	. 180	hauling mix to keep paver going steady	
32	Asphalt Plant Inspection	24	29	- 5	121		
33	Weigh/Check Asphalt Mixture	34	44	-10	129		
34	Asphalt Paving Office	7	5	2	71		

			MANHOURS			
			USED TO		PERCENT	REMARKS*
CODE	PLANNING ACTIVITY	PLANNED	DATE	REMAINING	USED	
PCC PAV	ING					
41	Portland Cement Concrete Paving Insp.	0	0	0	0	
42	PCC Plant Paving	0	0	0	0	
43	Joint Repair Inspection	0	0	0	0	
44	PCC Paving Office	0	0	0	0	
STRUCTU	IRE		1			
51	Structure Staking	44	50	- 6	114.	
52	Structure Inspection	464	432	32	93	
53	PCC Plant Structure	288	98	-10	111	
54	Structure Office	128	125	3	98	
MISCELL	ANEOUS					
61	Staking for Miscellaneous Items	23	20	3	87	
62	Inspection for Misc. Lems	30	35	5	117	
63	Office Work for Misc. Itens	34	30	4	88	
64	R/W Staking and Monumentation					
65	Staking Turn Lanes					
66	Inspection for Turn Lanes					
67	Office Work for Kurn Lanes					
SPECIAL	FEATURES					
71	Special Feature Staking	0	0	0	0	
72	Special Feature Inspection	0	0	0	0	
73	Special Feature Office	0	0	0	0	
GENERAL	· · · ·					
81	General Office Work	123	112	11	91	
82	Project Supervision & Management	161	150	11	93	
83	Standby	32	50	-18	188	2 breakdowns at bit. plant.
84	Travel	186	220	- 34	118	
85	Training & Equipment Maintenance	16	10	6	63	
	Total Project Activities	2008	2047	-39	102	

	1	Used to			Project is complete except for
	Planned	Date	Remaining	% Used	sodding and seeding and misc.
					cleanup
CONTRACT TIME (Working Days)	85	80.1	4.9	94%	
CONTRACTOR PAYMENTS (Dollars) (Estimated)	885,400	372,860		97%	

*The "Remarks" column is used to explain significant overruns, underruns, and to note completed items.

Original - A.D.E. Copy - Project Engineer - Project File Prepared by Project Engineer_____

• •

STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION HIGHWAY STATEWIDE

MONTHLY CONSTRUCTION PAYMENTS AND ENGINEERING COSTS

SAMPLE REPORT

•

DISTRICT		1	PERSONAL	ENCINEERING	;	
LOCATION	FUNDS	FUNDS	EXPENSE	COSTS	WORKING DAYS	MANHOURS
		USED			Wolderho Diffe	Inninoono
	ENCUMBERED	THIS	THIS PERIOD	THIS PERIOD	PLANNED	PLANNED
	CERTIFIED	PERIOD	TO DATE	TO DATE	USED TO DATE	USED TO DATE
PERIOD ENDING DATE	% CERTIFIED			% *	% USED	% USED
Duluth	\$3500000	<u> </u>	\$0	\$50000	4000	9000
Poriod Ending Data 10-00-91	\$XUBQBUU	\$200000	ŞU	\$150000	2500	6000
reitod Ending Date 10-09-01	$\int \sqrt{\sqrt{n}}$			1.5%	62.5%	66.6%
DISTRICT 2			¢0	¢20000	1500	0000
Bemidii	\$300000	\$150000	30 \$0	\$20000	4500	8000
Period Ending Date 10-09-81	66.6%	Q120000	ΨŪ	\$250000 8 3%	5000 66 6%	27 %
				0.5%	00.0%	07.6
	\$250000		<u> </u>	<u> </u>	2000	7500
Brainard	\$2500000	450000	ξ Ο	\$10000	3000	/500
Borind Ending Data 00-25-	\$2000000	\$20000	ŞU	\$200000	2500	6000
retrod Ending bale 09-23-64	80.0%			10.0%	83.3%	80.0%
DISTRICT 4	\$500000		\$0	\$50000	5000	10000
Detroit Lakes	\$2500000	\$300000	\$0 \$0	\$30000	2500	6000
Period Ending Date 09-25-81	¢2500000 50×0%	\$300000	ŶŬ	12.0%	2300 50 0%	60.0%
	20101			12.0%	50.0%	00.0%
District 5 😅	\$10000000		\$3500	\$150000	6000	15000
Golden Valley	\$6000000	\$1000000	\$15000	\$700000	4000	12000
Period Ending Date 10-9-81	60.0%			11.9%	66.6%	80.0%
District 6	\$800000		ŝŋ	\$20000	750	1250
Rochester	\$3500000	\$50000	90 \$0	920000 \$50000	150	1250
Period Ending Date 10-09-81	43 7%	\$20000	ŞU	30000	450	900
	-3.7%			14.26	00.0%	12.0%
					ł	
TOTALS	\$33500000	\$1750000	\$3500	\$300000	23250	50750
AVEDACE OF ALL DIGEDICES	\$19000000		\$15000	\$165000	14950	37900
AVERAGE OF ALL DISTRICTS	59.6%	I		10.7%	64.8%	74.3%

*Expressed as a % of funds certified

4

STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION HIGHWAY DISTRICT MONTHLY CONSTRUCTION PAYMENTS AND ENGINEERING COSTS

RESIDENT ENGINEER: DAVE TROOIEN

SAMPLE REPORT

LOW S.P. T.H.			PERSONAL	ENGINEERING		
LOCATION	FUNDS	FUNDS	EXPENSE	COSTS	WORKING DAYS	MANHOURS
		USED				
TYPE OF WORK:	ENCUMBERED	THIS	THIS PERIOD	THIS PERIOD	PLANNED	PLANNED
CONTRACTOR:	CERTIFIED	PERIOD	TO DATE	TO DATE	USED TO DATE	USED TO DATE
STARTING DATE//PERIOD ENDING	% CERTIFIED			% *	% USED	% USED
S.P. 0702 T.H. 14 On T.H. 14 from Eagle Lake to Waseca Seal Coat Miscellaneous Lindin Construction Co., Inc.	\$97497 \$97148	\$5000	\$0 \$171.24	\$6800	14 10	199 205
8/17/81 // 9/28/81 S.P. 0702-73 T.H. Completed	99.6%			7.0%	/1.4%	103.0%
District 7 Various Docations						
Safety & Traffic Control	\$129467		\$0	\$824	45	553
Dieseth Specialcy Co.	\$125075	\$7200	ş0	\$10036	38	581 105 1%
5/19/81 S.P. 0704-5959 Over Cobb River 5.3 Mile No. Jct. TH 30 & Over LeSueur River 5.3 Mi. So. Jct. 60 Deck Repairs	96.6%			8.0%	84.4%	103.1%
Reconstruction	\$465070		\$117.40	\$1406.40	85	1675
Glenwood Bridge, Inc.	\$348078	\$10000	\$642.80	\$18021	74	1081
6/15/81 // 10/6/81	74.8%			5.4%	87.0%	64.5%
TOTALS (PERIOD ENDING 10/6/81)	\$692034	\$22200	\$117.40	\$2230.40	144	2427
	\$570301	}	\$814.04	\$34857	122	1867
AVERAGE % 3 PROJECTS	82.4%			6.8%	80.9%	90.9%

*Expressed as a % of funds certified.

4



